



FED. ROAD REG. NO.	STATE	FEDERAL AID PROJECT NO.	SHEET NO.	TOTAL SHEETS
1	N.Y.	0146001	62	92
BENNINGTON CONNECTOR S.H. 98-2				
P.I.N. 1306.60				
WHITEHOUSE BRIDGE - VERMONT STATE LINE S.H. 1426				
RENSSELAER COUNTY				

* PAYMENT FOR ALL VERMONT ROUTES 279 AND 9 SIGNS WILL BE MADE UNDER N.Y.S. M.U.T.C.D. NO. AND SIZE SHOWN. HOWEVER, SIGN MATERIALS, COLORS, LETTERING AND SPECIFICATIONS SHALL MEET THE REQUIREMENTS OF VERMONT STANDARD SHEET E-1368M INCLUDED IN THE SPECIAL PROVISIONS.

SIGNS TO BE INSTALLED						
ITEM NO.		SIGN SUPPORT, NUMBER REG'D PER SIGN	STATION LOCATION	TEXT	N.Y.S. M.U.T.C.D. NO.	APPROX. SIZE OF SIGN
SIGN PANEL	SIGN SUPPORT					
645.7102 M	645.81M	2	45+150.0, LT		M13-23X M13-21X M3-2X (MOD) M3-1X	600X300 600X300 750X600 600X600 (1.17 m ²)
645.7102 M	645.81M	1	42+082.0, LT		W1-3C	750X750 (0.56 m ²)
645.73 M	645.8106 M	2	43+180.0, RT		G1-3C M14-26X M14-26X M8-5C M8-5C M14-42X M14-42X	2400X1050 600X200 600X200 600X600 600X600 525X375 525X375 (3.87 m ²)
645.7102 M	645.81M	2	43+265.0, RT 43+265.0, LT		R5-26C (MOD.)	900X900 (0.81 m ²)
645.73 M	645.81M	1	143+320.0, LT		G1-2C	1950X750 (1.46 m ²)
645.73 M	645.8106 M	2	43+340.0, LT		G1-3C M14-26X M11-1C M8-5C M14-41X M14-41X	2400X1050 600X200 600X600 600X600 525X375 525X375 (3.75 m ²)
645.73 M	645.81M	2	44+960.0, LT		112-2C	1050X750 (0.79 m ²)
645.7102 M	645.81M	1	143+490.0, RT		W7-13C	300X900 (0.27 m ²)

SIGNS TO BE REMOVED		
ITEM NO.	STATION LOCATION	TEXT
647.01M	43+081.0, LT	
647.02 M	43+112.0, LT	

NOTE:
ALL DIMENSIONS IN MILLIMETERS UNLESS OTHERWISE NOTED.

SIGN TEXT DATA	
SURVEYED BY	C.H.A. & V.S.E. DATE 12/93
DESIGNED BY	D.W.E. DATE 2/04
DRAWN BY	C.A.K. DATE 2/04
CHECKED BY	T.P.K. DATE 2/04
DESIGN FILE NO.	NYSTD1.DGN
PROJ. NAME	BENNINGTON - HOOSICK D.P.I. 0146(1) C/1
PROJ. NO.	P.I.N. 1306.60
SHEET	62 OF 92 DWG NO. STD-2