FED. ROAD REG. NO.	STATE	FEDERAL AID PROJECT NO.	SHEET NO.	TOTAL SHEETS
1	N.Y.	0146001	42	92

BENNINGTON CONNECTOR S.H. 98-2

P.I.N. 1306.60

WHITEHOUSE BRIDGE - VERMONT STATE LINE S.H. 1426

RENSSELAER COUNTY

GUIDE RAIL TABLE

LOCATION	POST SPACING	PAYMENT FACTOR	ITEMS								
			606.10 M	606.100001 M	606.1201 M	606.1202 M	606.1203 M	606.61 M	606.70 M	606.79 M	606.7910 M
			m	m	EA	EA	EA	m	m	EA	EA
S.H. 1426											
42+905.0 TO 42+920.0, RT							1				
42+920.0 TO 43+034.0, RT	1.83 m	1.0	~~114.0~~								
43+034.0, TO CA0+017.8, RT	1.83 m	1.0		20.1							
CA0+017.8 TO CA0+026.0, RT					~~1~~	~~1~~					
			120.7								
42+943.0, RT										1	
42+943.0 TO 43+015.0, RT									72		
43+015.0, RT								51.2		1	
			257.8								
43+165.0, RT											~~1~~
43+165.0 TO 43+~~215.0, RT~~ 340 RT								~~60~~			
43+215.0, RT						~~1~~					~~1~~
S.H. 1426 (STEM SECTION)											
CA0+024.0 TO CA0+026.0, RT					1						
CA0+026.0 TO 43+077.2, RT	1.83 m	1.0		26.2							
43+077.2 TO 43+215.8, RT	1.83 m	1.0	138.6								
43+215.8 TO 143+255.2, RT	1.83 m	1.0		28.3							
143+255.2 TO 143+354.6, RT	1.83 m	1.0	99.4								
143+354.6 TO 143+362.8, RT						1					
143+386.0 TO 143+390.0, RT						1					
143+390.0 TO 143+504.0, RT	1.83 m	1.0	109.8								
143+266.4 TO 143+274.0, LT							1				
143+274.0 TO 143+661.6, LT	1.83 m	1.0	372.8								
143+661.6 TO 143+669.2, LT							1				
143+263.0, RT											1
143+263.0 TO 143+504, RT								241			
	TOTAL		~~834.6~~ 743	~~74.6~~ 183	2	~~2~~ 4	3	301	72	2	~~3~~ 1

GUIDE RAIL ITEMS

ITEM NO.	DESCRIPTION
606.10 M	BOX BEAM GUIDE RAILING (m)
606.100001 M	BOX BEAM GUIDE RAILING (SHOP CURVED) (m)
606.1201 M	BOX BEAM GUIDE RAILING END ASSEMBLY TYPE I (EA)
606.1202 M	BOX BEAM GUIDE RAILING END ASSEMBLY TYPE II (EA)
606.1203 M	BOX BEAM GUIDE RAILING END ASSEMBLY TYPE III (EA)
606.61 M	REMOVING AND STORING CORRUGATED BEAM GUIDE RAILING (m)
606.70 M	REMOVING AND DISPOSING CABLE GUIDE RAILING (m)
606.79 M	REMOVING AND DISPOSING ANCHORAGE UNITS FOR CABLE GUIDE RAILING (EA)
606.7910 M	REMOVING AND DISPOSING ANCHORAGE UNITS FOR CORRUGATED BEAM GUIDE RAILING AND MEDIAN BARRIER (EA)

GUIDE RAIL TABLES

SURVEYED BY C.H.A. & V.S.E. DATE 12/93
DESIGNED BY D.W.E. DATE 2/04
DRAWN BY C.A.K. DATE 2/04
CHECKED BY T.P.K. DATE 2/04

DESIGN FILE NO. NYT-1.DGN

PROJ. NAME BENNINGTON - HOOSICK D.P.I. 0146(1) C/1

PROJ. NO. P.I.N. 1306.60

SHEET 42 OF 92 DWG NO. GT-1

IN CHARGE OF T. KARIS DESIGNED BY D. EMERICH CHECKED BY D. GOZALKOWSKI DRAFTED BY D. GOZALKOWSKI CHECKED BY C. KAHLBAUGH ESTIMATED BY D. EMERICH CHECKED BY T. BURTNICK DATE 2/04

FILE NAME = u:\5116\nysdot\contracts1\nyt-1.dgn
DATE/TIME = 2/23/2004
USER = 2225