

QUANTITY SHEET



SUMMARY OF ESTIMATED QUANTITIES														DETAILED SUMMARY OF QUANTITIES									
						NON GOV'T PARTICIPATING	EMPLOYEE TRAINEESHIP	BORROW AREA	EROSION CONTROL	BRIDGE 300	BRIDGE 400	BRIDGE 500	BRIDGE 600	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NUMBER	RND	QUANTITIES	UNIT	ITEMS	
																	BEGIN 600 mm OPTION PIPES						
						-	-	-	-	-	-	-	-	130	130	m	600 mm CAAP 1.52 mm (68 mm x 12 mm)	60L0225	-				
						-	-	-	-	-	-	-	-	130	130	m	600 mm PCCSP 1.63 mm (68 mm x 12 mm)	60L0425	-				
						-	-	-	-	-	-	-	-	130	130	m	600 mm CPEP	60L0920	-				
						-	-	-	-	-	-	-	-	130	130	m	600 mm CPEP (SL)	60L2620	-				
																	END 600 mm OPTION PIPES						
																	BEGIN 900 mm OPTION PIPES						
						-	-	-	-	-	-	-	-	39	39	m	900 mm CAAP 1.91 mm (68 mm x 12 mm)	60L0246	-				
						-	-	-	-	-	-	-	-	39	39	m	900 mm PCCSP 2.01 mm (68 mm x 12 mm)	60L0446	-				
						-	-	-	-	-	-	-	-	39	39	m	900 mm PCCSP (PI) 2.01 mm (68 mm x 12 mm)	60L0646	-				
						-	-	-	-	-	-	-	-	39	39	m	900 mm RCP CLASS III	60L0845	-				
						-	-	-	-	-	-	-	-	39	39	m	900 mm CPEP	60L0930	-				
						-	-	-	-	-	-	-	-	39	39	m	900 mm CPEP (SL)	60L2630	-				
																	END 900 mm OPTION PIPES						
																	BEGIN 1200 mm OPTION PIPES						
						-	-	-	-	-	-	-	-	66	66	m	1200 mm PCCSP 2.77 mm (68 mm x 12 mm)	60L0457	-				
						-	-	-	-	-	-	-	-	66	66	m	1200 mm PCCSP (PI) 2.77 mm (68 mm x 12 mm)	60L0657	-				
						-	-	-	-	-	-	-	-	66	66	m	1200 mm RCP CLASS III	60L0855	-				
																	END 1200 mm OPTION PIPES						
																	BEGIN 300 mm OPTION ELBOWS						
						-	-	-	-	-	-	-	-	30	30	EA	300 mm CAAP ELBOW 1.52 mm (68 mm x 12 mm)	60L5205	-				
						-	-	-	-	-	-	-	-	30	30	EA	300 mm PCCSP ELBOW 1.63 mm (68 mm x 12 mm)	60L5405	-				
						-	-	-	-	-	-	-	-	30	30	EA	300 mm CPEP ELBOW	60L5802	-				
																	END 300 mm OPTION ELBOWS						
																	BEGIN 450 mm OPTION ELBOWS						
						-	-	-	-	-	-	-	-	8	8	EA	450 mm CAAP ELBOW 1.52 mm (68 mm x 12 mm)	60L5215	-				
						-	-	-	-	-	-	-	-	8	8	EA	450 mm PCCSP ELBOW 1.63 mm (68 mm x 12 mm)	60L5415	-				
						-	-	-	-	-	-	-	-	8	8	EA	450 mm CPEP ELBOW	60L5814	-				
																	END 450 mm OPTION ELBOWS						
																	BEGIN 600 mm OPTION ELBOWS						
						-	-	-	-	-	-	-	-	2	2	EA	600 mm CAAP ELBOW 1.52 mm (68 mm x 12 mm)	60L5225	-				
						-	-	-	-	-	-	-	-	2	2	EA	600 mm PCCSP ELBOW 1.63 mm (68 mm x 12 mm)	60L5425	-				
						-	-	-	-	-	-	-	-	2	2	EA	600 mm CPEP ELBOW	60L5824	-				
																	END 600 mm OPTION ELBOWS						
																	BEGIN 300 mm OPTION PIPE END SECTIONS						
						-	-	-	-	-	-	-	-	15	15	EA	300 mm CSPES 1.63 mm (68 mm x 12 mm)	60L6005	-				
						-	-	-	-	-	-	-	-	15	15	EA	300 mm CPEPES	60L7005	-				
																	END 300 mm OPTION PIPE END SECTIONS						
																	BEGIN 450 mm OPTION PIPE END SECTIONS						
						-	-	-	-	-	-	-	-	4	4	EA	450 mm CSPES 1.63 mm (68 mm x 12 mm)	60L6015	-				
						-	-	-	-	-	-	-	-	4	4	EA	450 mm CAAPES 1.52 mm (68 mm x 12 mm)	60L6215	-				
						-	-	-	-	-	-	-	-	4	4	EA	450 mm CPEPES	60L7015	-				
																	END 450 mm OPTION PIPE END SECTIONS						
																	BEGIN 600 mm OPTION PIPE END SECTIONS						
						-	-	-	-	-	-	-	-	1	1	EA	600 mm CSPES 1.63 mm (68 mm x 12 mm)	60L6025	-				
						-	-	-	-	-	-	-	-	1	1	EA	600 mm CAAPES 1.52 mm (68 mm x 12 mm)	60L6225	-				
																	END 600 mm OPTION PIPE END SECTIONS						

PROJECT: BENNINGTON - HOOSICK PROJECT NO.: D.P.I. 0146(I) C/3
 DESIGN FILE NAME: 5116/VAOT/CON3/QUAN.DGN IPARM FILE NAME: N/A
 SURVEYED BY: N/A SURVEY DATE: N/A PLOT DATE: 11/01
 SQUAD LEADER: T.P.K. DRAWN BY: E.C.D.
 DWG. NO. Q-3 SHEET: 6 OF 473