STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET

VAOT Metric

SUMMARY OF ESTIMATED QUANTITIES

						NON GOV'T PARTICIPATING	EMPLOYEE TRAINEESHIP	BORROW AREA	EROSION CONTROL	BRIDGE 300	BRIDGE 400	BRIDGE 500	BRIDGE 600	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NUMBER	RND
																	BEGIN 900 mm OPTION PIPE END SECTIONS		
						-	-	-	-	-	-	-	-	3	3	EA	900 mm CSPES 2.01 mm (68 mm. x 12 mm)	601.6046	-
						-	-	-	-	-	-	-	-	3	3	EA	900 mm CAAPES 1.91 mm (68 mm x 12 mm)	601.6246	-
						-	-	-	-	-	-	-	-	3	3	EA	900 mm RCPES CLASS III	601.6845	-
																	END 900 mm OPTION PIPE END SECTIONS		
																	BEGIN 1200 mm OPTION PIPE END SECTIONS		
						-	-	-	-	-	-	-	-	2	2	EA	1200 mm CSPES 2.77 mm (68 mm x 12 mm)	601.6057	-
						-	-	-	-	-	-	-	-	2	2	EA	1200 mm CAAPES 2.67 mm (68 mm x 12 mm)	601.6257	-
						-	-	-	-	-	-	-	-	2	2	EA	1200 mm RCPES CLASS III	601.6855	-
																	END 1200 mm OPTION PIPE END SECTIONS		
						-	-	-	-	-	-	-	-	47	47	m	450 mm PCCSP 1.63 mm (68 mm x 12 mm)	601.0415	-
						-	-	-	-	-	-	-	-	2	2	m	600 mm PCCSP 1.63 mm (68 mm x 12 mm)	601.0425	-
						-	-	-	-	-	-	-	-	2	2	m	750 mm PCCSP 2.01 mm (68 mm x 12 mm)	601.0436	-
						-	-	-	-	-	-	-	-	39	39	m	1350 mm PCCSP 2.01 mm (75 mm x 25 mm)	601.0526	-
						-	-	-	-	-	-	-	-	2	2	m	1800 mm PCCSP 2.77 mm (75 mm x 25 mm)	601.0542	-
						-	-	-	-	-	-	-	-	1	1	m	1800 mm PCCSP 2.77 mm (75 mm x 25 mm) (MOD.)	601.0542	-
						-	-	-	-	-	-	-	-	2	2	EA	450 mm CSPES 1.63 mm (68 mm x 12 mm)	601.6015	-
						-	-	-	-	-	-	-	-	33	33	EA	CAST IRON GRATE WITH FRAME, TYPE E	604.48	-
						-	-	-	-	-	-	-	-	830	830	m	150 mm UNDERDRAIN (MOD.)	605.10	6
						-	-	-	-	-	-	-	-	135	135	m	150 mm UNDERDRAIN CARRIER PIPE	605.20	-
						-	-	-	-	-	-	-	-	21	21	EA	UNDERDRAIN FLUSHING BASINS	605.95	-
						-	-	-	-	-	870	-	-	-	870	m^2	REINFORCED SOIL SLOPE	612.20	-
						-	-	266	183	-	-	-	67	3214	3730	m^3	STONE FILL, TYPE I	613.10	4
						-	-	-	2758	115	277	-	-	9230	12380	m^3	STONE FILL, TYPE II	613.11	3
						-	-	-	2550	-	-	-	-	-	2550	m^3	STONE FILL, TYPE II (MOD.)	613.11	6
						-	-	-	-	-	548	1	1	-	550	m^3	STONE FILL, TYPE III	613.12	5
						-	-	-	-	204	-	-	-	836	1040	m^3	STONE FILL, TYPE IV	613.13	4
						-	-	-	-	-	-	-	-	710	710	m	GRANITE SLOPE EDGING	616.20	3.9
						-	-	-	-	-	48.8	48.8	48.4	-	146	m	PRECAST REINFORCED CONCRETE CURB, TYPE B	616.26	-
						-	-	-	-	-	-	-	-	1920	1920	m	TREATED TIMBER CURB	616.35	4.2
						-	-	-	-	-	-	-	-	14	14	t	BITUMINOUS CONCRETE GUTTERS & TRAFFIC ISLANDS	616.47	-
						-	-	-	-	-	-	-	-	69	69	EA	YIELDING MARKER POSTS	619.17	-
						-	-	790	-	-	-	-	-	-	790	m	CHAIN-LINK FENCE (TYPE I), 1.8 m	620.12	4
						-	-	-	-	-	-	-	-	575	575	m	CHAIN-LINK FENCE, 2.4 m	620.13	1.9

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

FILE NAME =u:\5116\VAOT\CONTRACT3\quan.dgn
DATE/TIME =10/16/2001
USER =664

PROJECT: BENNINGTON - HOOSICK	PROJECT NO.: D.P.I. 0146(1) C/3
DESIGN FILE NAME: 5116/VAOT/CON3/QUAN.DGN	
IPARM FILE NAME: N/A	PLOT DATE: 11/01
SURVEYED BY: N/A	SURVEY DATE: N/A
SQUAD LEADER: T.P.K.	DRAWN BY: E.C.D.
DWG. NO. 0-4	SHEET: 7 OF 473