STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET

VAOT Metric

SUMMARY OF ESTIMATED QUANTITIES

						NON GOV'T PARTICIPATING	EMPLOYEE TRAINEESHIP	BORROW AREA	EROSION CONTROL	BRIDGE 300	BRIDGE 400	BRIDGE 500	BRIDGE 600	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NUMBER	RND
						-	-	-	-	-	-	-	-	515	515	m	CHAIN-LINK FENCE, 2.4 m (MOD.)	620.13	1
						-	-	6	-	-	-	-	-	-	6	m	GATE FOR CHAIN-LINK FENCE (TYPE I), 1.8 m	620.16	-
						-	-	10	-	-	-	-	-	-	10	EA	BRACING ASSEMBLY FOR CHAIN-LINK FENCE, 1.8 m	620.21	-
						-	-	-	-	-	-	-	-	26	26	EA	BRACING ASSEMBLY FOR CHAIN-LINK FENCE, 2.4 m	620.22	-
						-	-	-	-	-	-	-	-	8460	8460	m	WOVEN WIRE FENCE WITH STEEL POSTS	620.25	21.6
						-	-	-	-	-	-	-	-	2	2	EA	DRIVE GATE FOR WOVEN WIRE FENCE (MOD.)	620.30	-
						-	-	-	-	-	-	-	-	160	160	EA	STEEL BRACE FOR WOVEN WIRE FENCE	620.40	1
						-	-	290	445	-	-	-	-	-	735	m	SNOW FENCE (MOD.)	620.70	2
						-	-	-	-	-	-	-	29	-	29	m	SNOW BARRIER - GALVANIZED	620.75	-
						-	-	-	-	-	-	-	-	4632.9	4632.9	m	STEEL BEAM GUARDRAIL	621.20	-
						-	-	-	-	-	-	-	-	12	12	EA	MANUFACTURED TERMINAL SECTION (FLARED)	621.505	-
						-	-	-	-	-	-	-	-	12	12	EA	GUARDRAIL APPROACH SECTION, NETC 2 RAIL (MOD.)	621.72	-
						-	-	-	-	-	7	6	-	-	13	EA	SETTLEMENT PLATFORM, TYPE 1	623.21	-
						-	-	-	-	-	2	-	-	-	2	EA	SETTLEMENT PLATFORM, TYPE 2	623.23	-
						-	-	-	-	-	24	-	-	-	24	m	INCLINOMETER	623.30	-
						-	-	-	-	-	-	-	-	~~64~~	~~64~~	~~HR~~	~~PUMP TEST FOR YIELD~~ ITEM NOT USED	~~626.30~~	-
						-	-	-	-	-	-	-	-	200	200	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.
						-	-	2536	-	-	-	-	-	1964	4500	HR	FLAGGERS	630.15	EST.
						-	2080	-	-	-	-	-	-	-	2080	HR	EMPLOYEE TRAINEESHIP	634.10	-
						-	-	-	-	-	0.05	0.05	0.05	0.85	1	LS	MOBILIZATION	635.10	-
						-	-	-	-	-	-	-	-	1	1	LS	TRAFFIC CONTROL	641.10	-
						-	-	-	-	-	-	-	-	6	6	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-
						-	-	-	-	-	-	-	-	~~11430~~	~~11430~~	~~m~~	~~DURABLE 100 mm WHITE LINE~~ ITEM NOT USED - SEE ITEM 646.414	~~646.40~~	7
						-	-	-	-	-	-	-	-	~~7850~~	~~7850~~	~~m~~	~~DURABLE 100 mm YELLOW LINE~~ ITEM NOT USED - SEE ITEM 646.415	~~646.41~~	9
						-	-	-	-	-	-	-	-	270	270	m	DURABLE 300 mm WHITE LINE	646.44	-
						-	-	-	-	-	-	-	-	~~1390~~	~~1390~~	~~EA~~	~~LINE STRIPING TARGETS~~ ITEM NOT USED	~~646.76~~	-
						-	-	-	-	-	-	-	-	25	25	m	PAINTED CURB	646.81	-

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT: BENNINGTON - HOOSICK

PROJECT NO.: D.P.I. 0146(1) C/3

DESIGN FILE NAME: 5116/VAOT/CON3/QUAN.DGN
IPARM FILE NAME: N/A
SURVEYED BY: N/A
SQUAD LEADER: T.P.K.
DWG. NO. Q-5

PLOT DATE: 11/01
SURVEY DATE: N/A
DRAWN BY: E.C.D.
SHEET: 8 OF 473

FILE NAME =u:\5116\VAOT\CONTRACT3\quan.dgn
DATE/TIME =10/15/2001
USER =664