STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET

VAOT Metric

SUMMARY OF ESTIMATED QUANTITIES

						NON GOV'T PARTICIPATING	EMPLOYEE TRAINEESHIP	BORROW AREA	EROSION CONTROL	BRIDGE 300	BRIDGE 400	BRIDGE 500	BRIDGE 600	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NUMBER	RND
						-	-	1412	-	-	-	-	-	91018	92430	m^2	GEOTEXTILE FOR ROADBED SUBGRADE SEPARATOR	649.11	4
						-	-	647	4761	354	821	18	201	31343	38145	m^2	GEOTEXTILE UNDER STONE FILL	649.31	4
						-	-	-	4240	-	-	-	-	-	4240	m^2	GEOTEXTILE UNDER STONE FILL (MOD.)	649.31	-
						-	-	-	-	-	-	-	-	5125	5125	m^2	GEOTEXTILE FOR UNDERDRAIN TRENCH LINING	649.41	1
						-	-	-	5685	-	-	-	-	-	5685	m^2	GEOTEXTILE FOR SILT FENCE	649.51	-
						-	-	72	-	-	-	-	-	1078	1150	kg	SEED	651.15	7
						-	-	48	722	-	-	-	-	-	770	kg	SEED - WINTER RYE	651.17	6
						-	-	572	-	-	-	-	-	8578	9150	kg	FERTILIZER	651.18	10
						-	-	5	-	-	-	-	-	~~69~~	~~74~~	~~t~~	~~AGRICULTURAL LIMESTONE~~ ITEM NOT USED	~~651.20~~	-
						-	-	5	-	-	-	-	-	69	74	t	HAY MULCH	651.25	-
						-	-	680	7080	-	-	-	-	-	7760	EA	HAY BALES FOR EROSION CONTROL	651.26	4
						-	-	-	-	-	-	-	-	715	715	m^3	TOPSOIL	651.35	5
						-	-	-	-	210	-	-	-	215	425	m^2	GRUBBING MATERIAL	651.40	3
						-	-	130	-	-	930	-	-	-	1060	m^2	EROSION MATTING	654.10	6
						-	-	-	-	-	-	-	-	46.49	46.49	m^2	TRAFFIC SIGNS, TYPE A	675.20	-
						-	-	-	-	-	-	-	-	107.19	107.19	m^2	TRAFFIC SIGNS, TYPE B	675.21	-
						-	-	-	-	-	-	-	-	279.2	279.2	m	FLANGED CHANNEL SIGN POSTS	675.301	-
						-	-	-	-	-	-	-	-	3284.1	3284.1	kg	W-SHAPE STEEL SIGN POSTS	675.31	-
						-	-	-	-	-	-	-	-	123.8	123.8	kg	TUBULAR ALUMINUM SIGN POSTS	675.32	-
						-	-	-	-	-	-	-	-	659.7	659.7	kg	TUBULAR STEEL SIGN POSTS	675.33	-
						-	-	-	-	-	-	-	-	9	9	EA	FOUNDATION FOR W-SHAPE STEEL POSTS, 750 mm DIAMETER	675.42	-
						-	-	-	-	-	-	-	-	12	12	EA	FOUNDATION FOR TUBULAR STEEL POSTS	675.43	-
						-	-	-	-	-	-	-	-	52	52	EA	DELINEATORS W/STEEL POSTS	676.10	-
						-	-	-	-	-	-	-	-	114.7	114.7	m	ELECTRICAL CONDUIT (50 mm DIA. - SCHEDULE 40)	678.21	-
						-	-	-	-	-	-	-	-	55	55	m	ELECTRICAL CONDUIT (75 mm DIA. - SCHEDULE 40)	678.21	-
						-	-	-	-	-	-	-	-	55	55	m	ELECTRICAL CONDUIT (75 mm DIA. - SCHEDULE 80)	678.21	-
						-	-	-	-	-	-	-	-	110	110	m	ELECTRICAL CONDUIT (100 mm DIA. - SCHEDULE 40)	678.21	-
						-	-	-	-	-	-	-	-	114.7	114.7	m	WIRED CONDUIT (75 mm DIA. - SCHEDULE 80)	678.23	-
						-	-	-	-	-	-	-	-	4	4	EA	JUNCTION BOX	678.26	-

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT: BENNINGTON - HOOSICK

PROJECT NO.: D.P.I. 0146(1) C/3

DESIGN FILE NAME: 5116/VAOT/CON3/QUAN.DGN
IPARM FILE NAME: N/A
SURVEYED BY: N/A
SQUAD LEADER: T.P.K.
DWG. NO. 0-6

PLOT DATE: 11/01
SURVEY DATE: N/A
DRAWN BY: E.C.D.
SHEET: 9 OF 473

FILE NAME =u:\5116\VAOT\CONTRACT3\quan.dgn
DATE/TIME =10/17/2001
USER =664