STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET

VAOT Metric

SUMMARY OF ESTIMATED QUANTITIES

						NON GOV'T PARTICIPATING	EMPLOYEE TRAINEESHIP	BORROW AREA	EROSION CONTROL	BRIDGE 300	BRIDGE 400	BRIDGE 500	BRIDGE 600	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NUMBER	RND
							*	THE FOLLOWING ITEMS ARE LISTED OUT OF ORDER WITH THE ITEMS ON THE PRECEDING SHEETS.											
																	BEGIN 450 mm OPTION PIPES		
						-	-	-	-	-	-	-	-	500	500	m	450 mm CAAP 1.52 mm (68 mm x 12 mm)	601.0215	-
						-	-	-	-	-	-	-	-	500	500	m	450 mm PCCSP 1.63 mm (68 mm x 12 mm)	601.0415	-
						-	-	-	-	-	-	-	-	500	500	m	450 mm CPEP	601.0915	-
						-	-	-	-	-	-	-	-	500	500	m	450 mm CPEP (SL)	601.2615	-
																	END 450 mm OPTION PIPES		
																	BEGIN 450 mm OPTION PIPES		
						-	-	-	-	-	-	-	-	121	121	m	450 mm CAAP 1.52 mm (68 mm x 12 mm)	601.0215	-
						-	-	-	-	-	-	-	-	121	121	m	450 mm PCCSP 1.63 mm (68 mm x 12 mm)	601.0415	-
						-	-	-	-	-	-	-	-	~~121~~	~~121~~	~~m~~	~~450 mm CPEP~~ ITEM NOT USED	~~601.0915~~	-
																	END 450 mm OPTION PIPES		
																	BEGIN 600 mm OPTION PIPES		
						-	-	-	-	-	-	-	-	17	17	m	600 mm CAAP 1.52 mm (68 mm x 12 mm)	601.0225	-
						-	-	-	-	-	-	-	-	17	17	m	600 mm PCCSP 1.63 mm (68 mm x 12 mm)	601.0425	-
						-	-	-	-	-	-	-	-	17	17	m	600 mm CPEP	601.0920	-
																	END 600 mm OPTION PIPES		
																	BEGIN 900 mm OPTION PIPES		
						-	-	-	-	-	-	-	-	54	54	m	900 mm CAAP 1.91 mm (68 mm x 12 mm)	601.0246	-
						-	-	-	-	-	-	-	-	54	54	m	900 mm PCCSP (PI) 2.01 mm (68 mm x 12 mm)	601.0646	-
						-	-	-	-	-	-	-	-	54	54	m	900 mm RCP CLASS III	601.0845	-
																	END 900 mm OPTION PIPES		

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT: BENNINGTON - HOOSICK	PROJECT NO.: D.P.I. 0146(I) C/3
DESIGN FILE NAME: 5116/VAOT/CON3/QUAN.DGN	
IPARM FILE NAME: N/A	PLOT DATE: 11/01
SURVEYED BY: N/A	SURVEY DATE: N/A
SQUAD LEADER: T.P.K.	DRAWN BY: E.C.D.
DWG. NO. Q-6A	SHEET: 9A OF 473