STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 2.8	50 3.2	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	MASS	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
VT. RTE 9 12+130.5, RT	Welcome To VERMONT	1	1500	1200	1.80						2												2	X										[SIGN ID CODE VD-421]	TSD-2	
12+175.0, RT	PROHIBITED	1	900	900	0.81						1			X																				[SIGN ID CODE VR-046]		E-142M
12+185.0, LT	REDUCED SPEED AHEAD	1	900	1200	1.08						1									X														[SIGN ID CODE R2-5A]		E-142M
12+215.0, RT	EAST	1	600	300	0.18						1			X																				[SIGN ID CODE M3-2]		E-136BM
	VERMONT 9 / VERMONT 279	1	900	900	0.81						1																							[SIGN ID CODE MI-5]		E-136BM
12+230.0, LT	TRUCK LANE ENDS	1	900	1200	1.08						1									X														[SIGN ID CODE VR-186]		E-141M
12+250.0, LT	AUTHORIZED VEHICLES ONLY	1	900	600	0.54						1			X																				[SIGN ID CODE VR-73IP]	TSD-2	
12+255.0, RT	SPEED LIMIT 60 / SPEED LIMIT 55	1	900	1200	1.08						1									X														[SIGN ID CODE R2-1]		E-142M
12+295.0, RT	WEIGH STATION NEXT RIGHT / CLOSED	1	2850	2400		6.84					2												2			X									TSD-4	
12+355.0, RT	SAFETY BELTS REQUIRED	1	1800	1800		3.24					2												2	X										[SIGN ID CODE VR-128]	TSD-2	
12+410.0, RT	AUTHORIZED VEHICLES ONLY	1	900	600	0.54						1			X																				[SIGN ID CODE VR-73IP]	TSD-2	
12+430.0, RT	LANE ENDS MERGE LEFT	1	900	900	0.81						2			X																				[SIGN ID CODE W9-2L]	TSD-1	
	1000 FEET	1	600	450	0.27																														TSD-1	
12+452.3, RT	0090 0202 0020 0279	1	150	200	0.03						1	X																						[SIGN ID CODE VD-700]		E-138M
												m 2.5	m	m 25.9	m	m	m	EA		kg 21.9	kg	kg		kg 192.5	kg	kg 164.2	kg								
TOTALS					m^2 9.03	m^2 10.08	EA.	m^2				m 28.4			m					kg 21.9			EA. 6	kg 356.7				EA.	EA.	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

AS-BUILT NOTE: REFERENCE CONTRACT C/6, CHANGE OF DESIGN #4 FOR CONTRACT C/3 REVISIONS.

PROJECT: BENNINGTON - HOOSICK	PROJECT NO.: D.P.I. 0146(1) C/3
DESIGN FILE NAME:	
IPARM FILE NAME: N/A	PLOT DATE: 11/01
SURVEYED BY: N/A	SURVEY DATE: N/A
SQUAD LEADER: T.P.K.	DRAWN BY: E.C.D.
DWG. NO. TSS-1	SHEET: 158 OF 473

FILE NAME =u:\5116\VAOT\CONTRACT3\TSS-1.DGN
DATE/TIME =10/11/2001
USER =664