STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (mm)	SIGN DIMENSIONS HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	FLANGED CHANNEL kg/m 3.0	FLANGED CHANNEL kg/m 4.5	SQUARE STEEL (mm) kg/m 44 2.8	SQUARE STEEL (mm) kg/m 50 3.2	SQUARE STEEL (mm) kg/m 63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	TUBULAR ALUMINUM Ø (mm) kg/m 100 2.5	TUBULAR ALUMINUM Ø (mm) kg/m 100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUND-ATION	TUBULAR STEEL Ø (mm) kg/m 75 11.3	TUBULAR STEEL Ø (mm) kg/m 89 13.4	TUBULAR STEEL Ø (mm) kg/m 100 16.1	TUBULAR STEEL Ø (mm) kg/m 125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	W-SHAPE STEEL FTG. SIZE 750 mm	W-SHAPE STEEL MASS	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
VT. RTE 9 12+458.6, LT	LANE ENDS MERGE LEFT	1	900	900	0.81						2			X																				[SIGN ID CODE W9-2L]	TSD-1	
12+~~470.0~~ 600.0, RT	EXIT 25 M.P.H.	1	600	750	0.45						1			X																				[SIGN ID CODE W13-2]		E-150M
12+744.0, RT		1	450	450	0.20						1	X																						[SIGN ID CODE OM-1]		E-150M
12+745.0, RT	WEIGH STATION ↗	1	1650	1500		2.48																	2	X											TSD-4	
12+774.2, LT	~~0090~~ 0279 0202 0040	1	150	200	0.03						1	X																						[SIGN ID CODE VD-700]		E-138M
12+804.0, RT	WRONG WAY	1	900	600	0.54						1			X																				[SIGN ID CODE R5-1A]		E-143M
12+805.0, RT	WRONG WAY	1	900	600	0.54						1			X																				[SIGN ID CODE R5-1A]		E-143M
12+880.0, RT	DO NOT ENTER	1	750	750	0.56						1			X																				[SIGN ID CODE R5-1]		E-143M
12+880.0, RT	DO NOT ENTER	1	750	750	0.56						1			X																				[SIGN ID CODE R5-1]		E-143M
12+920.0, RT	TRUCK LANE ENDS	1	900	1200	1.08						1									X														[SIGN ID CODE VR-186]		E-141M
12+980.0, RT		1	450	450	0.20						1	X																						[SIGN ID CODE OM-1]		E-150M
13+085.0, RT	UNSAFE TO PASS	1	900	900	0.81						2			X																				[SIGN ID CODE VW-092]		E-150M
13+096.1, RT	~~0090~~ 0279 0202 0060	1	150	200	0.03						1	X																						[SIGN ID CODE VD-700]		E-138M
												m 14.1	m	m 38.8	m	m	m		EA	kg 7.3	kg	kg		kg 96.2	kg	kg	kg								
TOTALS					m² 5.81	m² 2.48	EA.	m²				m 52.9			m					kg 7.3			EA. 2	kg 96.2				EA.	EA.	kg					

RMT 2/3/06

AS-BUILT NOTE: SEE NOTE ON SHEET 158

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT: BENNINGTON - HOOSICK
PROJECT NO.: D.P.I. 0146(1) C/3

DESIGN FILE NAME:
IPARM FILE NAME: N/A
SURVEYED BY: N/A
SQUAD LEADER: T.P.K.
DWG. NO. TSS-2

PLOT DATE: 11/01
SURVEY DATE: N/A
DRAWN BY: E.C.D.
SHEET: 159 OF 473

FILE NAME =u:\5116\VAOT\CONTRACT3\TSS-1.DGN
DATE/TIME =10/11/2001
USER =664