STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 2.8	50 3.2	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	FOUND-ATION	TUBULAR STEEL Ø (mm) kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	MASS	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
VT. RTE 9 13+971.0, RT	BRIDGE 1 VT ~~9~~ 279	1	150	200	0.03						1	X																					[SIGN ID CODE VD-701]		E-134M
13+992.0, LT	BRIDGE 1 VT ~~9~~ 279	1	150	200	0.03						1	X																					[SIGN ID CODE VD-701]		E-134M
14+055.0, RT	~~SPEED LIMIT 60~~ SPEED LIMIT 55	1	900	1200	1.08						1										X												[SIGN ID CODE R2-1]		E-142M
14+061.7, LT	~~0090~~ 0202 0120 0279	1	150	200	0.03						1	X																					[SIGN ID CODE VD-700]		E-138M
14+118.0, RT	BRIDGE 2 VT ~~9~~ 279	1	150	200	0.03						1	X																					[SIGN ID CODE VD-701]		E-134M
14+187.0, LT	BRIDGE 2 VT ~~9~~ 279	1	150	200	0.03						1	X																					[SIGN ID CODE VD-701]		E-134M
14+240.0, LT		1	900	900	0.81						2			X																			[SIGN ID CODE W6-3]		E-151M
14+240.0, RT		1	900	900	0.81						2			X																			[SIGN ID CODE W6-3]		E-151M
14+383.5, RT	~~0090~~ 0202 0140 0279	1	150	200	0.03						1	X																					[SIGN ID CODE VD-700]		E-138M
14+705.4, LT	~~0090~~ 0202 0160 0279	1	150	200	0.03						1	X																					[SIGN ID CODE VD-700]		E-138M
14+720.0, LT		1	900	900	0.81						2			X																			[SIGN ID CODE W6-3]		E-151M
14+720.0, RT		1	900	900	0.81						2			X																			[SIGN ID CODE W6-3]		E-151M
14+851.0, RT	BRIDGE 3 VT ~~9~~ 279	1	150	200	0.03						1	X																					[SIGN ID CODE VD-701]		E-134M
14+920.0, LT	BRIDGE 3 VT ~~9~~ 279	1	150	200	0.03						1	X																					[SIGN ID CODE VD-701]		E-134M
15+027.3, RT	~~0090~~ 0202 0180 0279	1	150	200	0.03						1	X																					[SIGN ID CODE VD-700]		E-138M
15+080.0, RT	Bennington NEXT 2 EXITS	1	2850	1050		2.99					2												2	X									[SIGN ID CODE E9]	TSD-3	
												m 27.0	m	m 38.8	m	m	m		EA	kg	kg 11.1	kg		kg 110.7	kg	kg	kg								
	TOTALS				m² 4.62	m² 2.99	EA.	m²				m 65.8			m						kg 11.1		EA. 2		kg 110.7			EA.	EA.	kg					

RMT 2/3/06

AS-BUILT NOTE: SEE NOTE ON SHEET 158

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT: BENNINGTON - HOOSICK
PROJECT NO.: D.P.I. 0146(1) C/3

DESIGN FILE NAME:
IPARM FILE NAME: N/A
SURVEYED BY: N/A
SQUAD LEADER: T.P.K.
DWG. NO. TSS-4

PLOT DATE: 11/01
SURVEY DATE: N/A
DRAWN BY: K.H.D.
SHEET: 161 OF 473

FILE NAME =u:\516\VAOT\CONTRACT3\TSS-1.DGN
DATE/TIME =10/11/2001
USER =664