STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

Not Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	NEW & SALVAGED SIGNS: SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	"A"	"B"	SALV SIGN	SALV TIS	EXIST POST: RETAIN	SALVAGE	NEW SIGN POSTS: NO. OF POSTS	FLANGED CHANNEL kg/m: 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m: 44 / 2.8	50 / 3.2	63 / 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m: 75 / 1.9	100 / 2.5	100 MOD / 2.5	TUBULAR STEEL Ø (mm): FOUNDATION	75 / 11.3	89 / 13.4	100 / 16.1	125 / 21.7	W-SHAPE STEEL FTG. SIZE: 600 mm	750 mm	MASS	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
VT. RTE 9 15+152.0, RT	BRIDGE 4 VT-~~9~~ 279	1	150	200	0.03						1	X																					[SIGN ID CODE VD-701]		E-134M
15+192.0, LT	BRIDGE 4 VT-~~9~~ 279	1	150	200	0.03						1	X																					[SIGN ID CODE VD-701]		E-134M
15+280.0, RT	UNSAFE TO PASS	1	900	900	0.81						2			X																			[SIGN ID CODE VW-092]		E-150M
15+349.1, LT	~~0090~~ 0202 0200 0279	1	150	200	0.03						1	X																					[SIGN ID CODE VD-700]		E-138M
15+480.0, LT	TRUCK LANE ENDS	1	900	1200	1.08						1										X												[SIGN ID CODE VR-186]		E-141M
15+520.0, RT	US TO VERMONT 7A Bennington North Bennington 1 MILE	1	7200	4450		32.04					3																		3	1234.8	W310X44.5		[SIGN ID CODE E1-1A) FUSE PLATE BOLT TENSION TO BE SET AT 143 kN.	TSD-3	
15+671.0, RT	UNSAFE TO PASS	1	900	900	0.81						2			X																			[SIGN ID CODE VW-092]		E-150M
	~~0090~~ 0202 0220 0279	1	150	200	0.03																												[SIGN ID CODE VD-700]		E-138M
15+708.6, LT	LANE ENDS MERGE LEFT	1	900	900	0.81						2			X																			[SIGN ID CODE W9-2L]	TSD-1	
15+760.0, RT		1	900	900	0.81						2			X																			[SIGN ID CODE W7-1]		E-152M
	5% GRADE	1	600	450	0.27																												[SIGN ID CODE W7-3]	TSD-1	
					m²	m²	EA.	m²				m			m					EA	kg				kg				EA.	EA.	kg					
					4.71	32.04						8.1		36.7								11.1								3	1234.8					
												44.8																								
															11.1																					

RMT 2/3/06

AS-BUILT NOTE: SEE NOTE ON SHEET 158

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

TOTALS

PROJECT:	PROJECT NO.:
BENNINGTON - HOOSICK	D.P.I. 0146(1) C/3
DESIGN FILE NAME:	
IPARM FILE NAME: N/A	PLOT DATE: 11/01
SURVEYED BY: N/A	SURVEY DATE: N/A
SQUAD LEADER: T.P.K.	DRAWN BY: E.C.D.
DWG. NO. TSS-5	SHEET: 162 OF 473

FILE NAME =u:\5116\VAOT\CONTRACT3\TSS-1.DGN
DATE/TIME =10/11/2001
USER =664