STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) 44 kg/m 2.8	50 kg/m 3.2	63 kg/m 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) 75 kg/m 1.9	100 kg/m 2.5	100 MOD kg/m 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	75 kg/m 11.3	89 kg/m 13.4	100 kg/m 16.1	125 kg/m 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	MASS	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
VT. RTE 9 15+992.9, LT	0090 0202 0240 0279	1	150	200	0.03						1	X																						[SIGN ID CODE VD-700]		E-138M
15+930.0 RT	BENNINGTON COLLEGE NEXT RIGHT	1	5400	2700		14.58																												INSTALLED ON EXISTING POSTS		
	BENNINGTON DOWNTOWN SECOND RIGHT																																		
16+075.0, RT	UNSAFE TO PASS	1	900	900	0.81						2			X																				[SIGN ID CODE VW-092]		E-150M
16+220.0, LT	WEST	1	600	300	0.18						1									X														[SIGN ID CODE M3-4]		E-136BM
	VERMONT 9 VERMONT 279	1	900	900	0.81																													[SIGN ID CODE MI-5]		E-136BM
16+225.4, RT	91 TO 7A HISTORIC Bennington North Bennington 1/2 MILE	1	7200	4450		32.04					3																			3	1054.7	W310X44.5		[SIGN ID CODE EI-1B] FUSE PLATE BOLT TENSION TO BE SET AT 143 kN.	TSD-3	
16+295.0 RT	NEXT 2 EXITS	1	2550	2100		5.36					2												2			X									
16+~~295.0~~, RT	UNSAFE TO PASS	1	900	900	0.81						~~2~~			~~X~~																				[SIGN ID CODE VW-092]		E-150M
16+314.8, RT	~~0090~~ 0202 0260 0279	1	150	200	0.03						1	X																						[SIGN ID CODE VD-700]		E-138M
~~16+355.0, RT~~	~~REDUCED SPEED AHEAD~~	1	900	1200	1.08						~~1~~									~~X~~														[SIGN ID CODE R2-5A]		E-142M
16+400.0, LT	SLOWER TRAFFIC KEEP RIGHT	1	900	1200	1.08						1										X													[SIGN ID CODE R4-3]		E-141M
~~16+415.0, RT~~	~~SPEED LIMIT 50~~	1	900	1200	1.08						~~1~~									~~X~~														[SIGN ID CODE R2-1]		E-142M
	~~UNLESS OTHERWISE POSTED~~	1	900	600	0.54																													[SIGN ID CODE VR-731P]	TSD-2	
												m 5.4	m	m 16.8	m	m	m	EA	kg 24.5	kg 11.1	kg		kg	kg	kg	kg								
TOTALS			m^2 6.45	m^2 32.04	EA.	m^2						m 22.2			m				kg 35.6			EA.	kg				EA. 3		kg 1054.7					

RMT 2/3/06

AS-BUILT NOTE: SEE NOTE ON SHEET 158

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT: BENNINGTON - HOOSICK
PROJECT NO.: D.P.I. 0146(1) C/3

DESIGN FILE NAME:
IPARM FILE NAME: N/A
SURVEYED BY: N/A
SQUAD LEADER: T.P.K.
DWG. NO. TSS-6

PLOT DATE: 11/01
SURVEY DATE: N/A
DRAWN BY: E.C.D.
SHEET: 163 OF 473

FILE NAME =u:\5116\VAOT\CONTRACT3\TSS-1.DGN
DATE/TIME = 10/11/2001
USER =664