STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET

Metric

SUMMARY OF ESTIMATED QUANTITIES

							NON GOV'T PARTICIPATING	EMPLOYEE TRAINEESHIP	BORROW AREA	EROSION CONTROL	BRIDGE 700	BRIDGE 900	BRIDGE 1000	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NUMBER	RND
																	BEGIN 450 mm OPTION PIPES		
							-	-	-	-	-	-	-	476	476	m	450 mm CAAP 1.6 mm (67 mm x 13 mm)	601.0215	-
							-	-	-	-	-	-	-	476	476	m	450 mm PCCSP 1.7 mm (67 mm x 13 mm)	601.0415	-
							-	-	16	-	-	-	-	444	460	m	450 mm RCP CLASS III	601.0815	-
							-	-	-	-	-	-	-	476	476	m	450 mm CPEP	601.0915	-
							-	-	55	-	-	-	-	422	477	m	450 mm CPEP (SL)	601.2615	-
																	END 450 mm OPTION PIPES		
																	BEGIN 750 mm OPTION PIPES		
							-	-	-	-	-	-	-	51	51	m	750 mm CAAP 2.0 mm (67 mm x 13 mm)	601.0236	-
							-	-	-	-	-	-	-	51	51	m	750 mm PCCSP 2.1mm (67 mm x 13 mm)	601.0436	-
							-	-	-	-	-	-	-	51	51	m	750 mm PCCSP (PI) 2.1mm (67 mm x 13 mm)	601.0636	-
							-	-	-	-	-	-	-	51	51	m	750 mm RCP CLASS III	601.0835	-
							-	-	-	-	-	-	-	51	51	m	750 mm CPEP	601.0925	-
							-	-	-	-	-	-	-	51	51	m	750 mm CPEP (SL)	601.2625	-
																	END 750 mm OPTION PIPES		
																	BEGIN 300 mm OPTION ELBOWS		
							-	-	-	-	-	-	-	6	6	EA	300 mm CAAP ELBOW 1.6 mm (67 mm x 13 mm)	601.5205	-
							-	-	-	-	-	-	-	6	6	EA	300 mm PCCSP ELBOW 1.7 mm (67 mm x 13 mm)	601.5405	-
							-	-	-	-	-	-	-	6	6	EA	300 mm CPEP ELBOW	601.5802	-
																	END 300 mm OPTION ELBOWS		
																	BEGIN 450 mm OPTION ELBOWS		
							-	-	-	-	-	-	-	2	2	EA	450 mm CAAP ELBOW 1.6 mm (67 mm x 13 mm)	601.5215	-
							-	-	-	-	-	-	-	2	2	EA	450 mm PCCSP ELBOW 1.7 mm (67 mm x 13 mm)	601.5415	-
							-	-	-	-	-	-	-	2	2	EA	450 mm CPEP ELBOW	601.5814	-
																	END 450 mm OPTION ELBOWS		
																	BEGIN 300 mm OPTION PIPE END SECTIONS		
							-	-	-	-	-	-	-	11	11	EA	300 mm CSPES 1.7 mm (67 mm x 13 mm)	601.6005	-
							-	-	-	-	-	-	-	11	11	EA	300 mm CPEPES	601.7005	-
																	END 300 mm OPTION PIPE END SECTIONS		
																	BEGIN 450 mm OPTION PIPE END SECTIONS		
							-	-	-	-	-	-	-	11	11	EA	450 mm CSPES 1.7 mm (67 mm x 13 mm)	601.6015	-
							-	-	-	-	-	-	-	11	11	EA	450 mm CAAPES 1.6 mm (67 mm x 13 mm)	601.6215	-
							-	-	2	-	-	-	-	11	13	EA	450 mm RCPES CLASS III	601.6815	-
							-	-	1	-	-	-	-	11	12	EA	450 mm CPEPES	601.7015	-
																	END 450 mm OPTION PIPE END SECTIONS		
																	BEGIN 750 mm OPTION PIPE END SECTIONS		
							-	-	-	-	-	-	-	2	2	EA	750 mm CSPES 2.1mm (67 mm x 13 mm)	601.6036	-
							-	-	-	-	-	-	-	2	2	EA	750 mm CAAPES 1.6 mm (67 mm x 13 mm)	601.6236	-
							-	-	-	-	-	-	-	2	2	EA	750 mm RCPES CLASS III	601.6835	-
							-	-	-	-	-	-	-	2	2	EA	750 mm CPEPES	601.7025	-
																	END 750 mm OPTION PIPE END SECTIONS		
							-	-	-	-	-	-	-	14	14	m	900 mm RCP CLASS III	601.0845	-
							-	-	-	-	-	-	-	4	4	EA	900 mm RCPES CLASS III	601.6845	-
							-	-	-	-	-	-	-	103	103	m	CLEANING CULVERT PIPE IN PLACE (0-600 mm INCLUSIVE)	601.995	0.5
							-	-	-	-	-	-	-	52	52	m	CLEANING CULVERT PIPE IN PLACE (0-600 mm INCLUSIVE) (MOD.)	601.995	0.7
							-	-	-	-	-	-	-	2	2	EA	SANITARY SEWER MANHOLE	604.22	-

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		SUPERPAVE BITUMINOUS CONCRETE PAVEMENT
		(PG 58-28) TYPE IS
225	†	VT. ROUTE 9
3540	†	RAMPS
114	†	VT. ROUTE 67A
506	†	DETOURS
4385	†	TOTAL
		SUPERPAVE BITUMINOUS CONCRETE PAVEMENT
		(PG 58-28) TYPE IIS
475	†	VT. ROUTE 9
3386	†	RAMPS
97	†	VT. ROUTE 67A
3958	†	TOTAL
		SUPERPAVE BITUMINOUS CONCRETE PAVEMENT
		(PG 58-28) TYPE IIIS
141	†	VT. ROUTE 9
2116	†	RAMPS
1658	†	VT. ROUTE 67A
203	†	SILK ROAD
352	†	DETOURS
4	†	DRIVES
4474	†	TOTAL
		SUPERPAVE BITUMINOUS CONCRETE PAVEMENT
		(PG 58-28) TYPE IVS
990	†	VT. ROUTE 67A
12	†	SILK ROAD
1002	†	TOTAL
		SUPERPAVE BITUMINOUS CONCRETE PAVEMENT
		(PG 58-28) SUMMARY
4385	†	TYPE IS
3958	†	TYPE IIS
4474	†	TYPE IIIS
1002	†	TYPE IVS
1	†	ROUNDING
13820	†	TOTAL

PROJECT: BENNINGTON - HOOSICK
PROJECT NO.: D.P.I. 0146(1) C/4

DESIGN FILE NAME: 5116/VAOT/CON4/QUAN.DGN
IPARM FILE NAME: N/A
SURVEYED BY: N/A
SQUAD LEADER: T.P.K.
DWG. NO. 0-3
PLOT DATE: 9/00
SURVEY DATE: N/A
DRAWN BY: E.C.D.
SHEET: 6 OF 385

FILE NAME =u:\5116\vaot\contract4\quan.dgn
DATE/TIME =11 SEP 2000
USER =1459