STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET

Metric

SUMMARY OF ESTIMATED QUANTITIES

NON GOV'T PARTICIPATING	EMPLOYEE TRAINEESHIP	BORROW AREA	EROSION CONTROL	BRIDGE 700	BRIDGE 900	BRIDGE 1000	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NUMBER	RND
-	-	-	-	-	-	-	5	5	EA	REHABING DI, CB, OR MH, CLASS I	604.412	-
-	-	-	-	-	-	-	2	2	EA	REHABING DI, CB, OR MH, CLASS II	604.415	-
-	-	-	-	-	-	-	5	5	EA	CHANGING ELEVATION OF SEWER MANHOLES	604.42	-
-	-	-	-	-	-	-	1	1	EA	CAST IRON GRATE WITH FRAME, TYPE A	604.45	-
-	-	1	-	-	-	-	11	12	EA	CAST IRON GRATE WITH FRAME, TYPE D	604.47	-
-	-	-	-	-	-	-	24	24	EA	CAST IRON GRATE WITH FRAME, TYPE E	604.48	-
-	-	-	-	-	-	-	216	216	m	150 mm UNDERDRAIN (MOD.)	605.10	-
-	-	-	-	-	-	-	48	48	m	150 mm UNDERDRAIN CARRIER PIPE	605.20	-
-	-	13	-	-	-	-	-	13	m	150 mm UNDERDRAIN CARRIER PIPE (SL)	605.20	-
-	-	-	-	-	-	-	10	10	EA	UNDERDRAIN FLUSHING BASINS	605.95	-
-	-	-	-	-	-	-	25	25	HR	POWER GRADER RENTAL	608.15	EST.
-	-	-	-	-	-	-	25	25	HR	ALL- PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.
-	-	-	-	-	-	-	15	15	HR	POWER BROOM RENTAL	608.30	EST.
-	-	-	-	-	-	-	15	15	HR	POWER BROOM RENTAL, TYPE II	608.31	EST.
-	-	-	-	-	-	-	25	25	HR	TRUCK RENTAL	608.37	EST.
-	-	-	-	-	-	-	25	25	HR	LOADER RENTAL, TYPE I	608.40	EST.
-	-	340	-	150	-	-	10	500	m^3	STONE FILL, TYPE I	613.10	3.5
-	-	-	424	-	66	-	540	1030	m^3	STONE FILL, TYPE II	613.11	4
-	-	-	3390	-	-	-	-	3390	m^3	STONE FILL, TYPE II (MOD.)	613.11	1
-	-	-	-	-	-	40	-	40	m^3	STONE FILL, TYPE III	613.12	-
-	-	-	-	2660	-	-	-	2660	m^3	STONE FILL, TYPE IV	613.13	-
-	-	-	-	-	-	-	1010	1010	m	GRANITE SLOPE EDGING	616.20	8
										BEGIN OPTION ITEM		
-	-	-	-	-	-	-	550	550	m	PRECAST REINFORCED CEMENT CONCETE CURB, TYPE B	616.26	3
-	-	-	-	-	-	-	550	550	m	CAST - IN - PLACE CEMENT CONCRETE CURB, TYPE B	616.28	3
										END OPTION ITEM		
-	-	-	-	-	-	-	560	560	m	TREATED TIMBER CURB	616.35	3.5
-	-	-	-	-	-	-	1010	1010	m	REMOVAL OF EXISTING CURB	616.41	3.5
-	-	-	-	-	-	-	47	47	t	BITUMINOUS CONCRETE GUTTERS AND TRAFFIC ISLANDS	616.47	-
-	-	2	-	-	-	-	37	39	EA	YIELDING MARKER POSTS	619.17	-
-	-	-	-	-	-	-	1750	1750	m	CHAIN-LINK FENCE, 1.8 m	620.12	8.4

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT: BENNINGTON - HOOSICK

PROJECT NO.: D.P.I. 0146(1) C/4

DESIGN FILE NAME: 5116/VAOT/CON4/QUAN.DGN
IPARM FILE NAME: N/A
SURVEYED BY: N/A
SQUAD LEADER: T.P.K.
DWG. NO. 0-4

PLOT DATE: 9/00
SURVEY DATE: N/A
DRAWN BY: E.C.D.
SHEET: 7 OF 385

FILE NAME =u:\5116\vaot\contract4\quan.dgn
DATE/TIME =11 SEP 2000
USER =1459