STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) 44 kg/m 2.8	50 kg/m 3.2	63 kg/m 5.0	ANCHOR	SLIP SLEEVE	TUBULAR ALUMINUM Ø (mm) 75 kg/m 1.9	100 kg/m 2.5	100 MOD kg/m 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	75 kg/m 11.3	89 kg/m 13.4	100 kg/m 16.1	125 kg/m 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	MASS	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
RAMP X X10+040.0, RT O/H	279 TO 7 Bennington Manchester	1	5500	4200		23.10																													TSD-1	
X10+100.0, RT		1	900	900	0.81						2			X																			[SIGN ID CODE W6-1]		E-151M
X10+142.0, LT		1	900	1200	1.08						2			X																			[SIGN ID CODE R4-7]		E-144M
		1 1	450 450	450 450	0.20 0.20																											[SIGN ID CODE OM-1] [SIGN ID CODE OM-1] BACK-TO-BACK		E-150M E-150M
X10+200.0, RT		1	900	900	0.81						2			X																			[SIGN ID CODE W4-1]		E-150M
X10+256.0, LT	ONE WAY	1	900	300	0.27						1		X																			[SIGN ID CODE R6-1R]		E-142M
RAMP Y Y10+100.0, LT		1	900	900	0.81						2			X																			[SIGN ID CODE W4-1]		E-150M
Y10+160.0, RT	WRONG WAY	1	900	600	0.54						1			X																			[SIGN ID CODE R5-1A] MOUNT SIGN FACING OPPOSING TRAFFIC		E-143M
Y10+160.0, LT	WRONG WAY	1 1	900 900	900 600	0.81 0.54						2			X																			[SIGN ID CODE W6-3] [SIGN ID CODE R5-1A] BACK-TO-BACK		E-151M E-143M
Y10+163.0, RT		1	900	900	0.81						2			X																			[SIGN ID CODE W6-3]		E-151M
												m	m 3.6	m 60.1	m	m	m		EA	kg	kg	kg		kg	kg	kg	kg								
TOTALS					m^2 6.88	m^2 23.10	EA.	m^2				m 63.7			m					kg			EA.	kg				EA.	EA.	kg						

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT:	PROJECT NO.:
BENNINGTON - HOOSICK	D.P.I. 0146(1) C/4
DESIGN FILE NAME:	
IPARM FILE NAME: N/A	PLOT DATE: 9/00
SURVEYED BY: N/A	SURVEY DATE: N/A
SQUAD LEADER: T.P.K.	DRAWN BY: E.C.D.
DWG. NO. TSS-2	SHEET: 138 OF 385

FILE NAME =u:\5116\vaot\contract4\tss-1.dgn
DATE/TIME =07 SEP 2000
USER =1459