STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

Not Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	FLANGED CHANNEL kg/m 3.0	FLANGED CHANNEL kg/m 4.5	SQUARE STEEL (mm) kg/m 44 2.8	SQUARE STEEL (mm) kg/m 50 3.2	SQUARE STEEL (mm) kg/m 63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	TUBULAR ALUMINUM Ø (mm) kg/m 100 2.5	TUBULAR ALUMINUM Ø (mm) kg/m 100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	TUBULAR STEEL Ø (mm) kg/m 75 11.3	TUBULAR STEEL Ø (mm) kg/m 89 13.4	TUBULAR STEEL Ø (mm) kg/m 100 16.1	TUBULAR STEEL Ø (mm) kg/m 125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	W-SHAPE STEEL FTG. SIZE 750 mm	W-SHAPE STEEL MASS	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
RAMP AB ABIO+122.8, RT		1	450	600	0.27						1		X																				[SIGN ID CODE WI-8]		E-150M
ABIO+125.3, RT		1	450	600	0.27						1		X																				[SIGN ID CODE WI-8]		E-150M
ABIO+140.0, LT	← N. BENNINGTON 3	1	1800	250	0.45						2												2	X									[SIGN ID CODE DI-1]	TSD-3	
	BENNINGTON 1 →	1	1800	250	0.45																												[SIGN ID CODE DI-1]	TSD-3	
	FOOD →	1	1350	185	0.25																														E-133M
	← PHONE →	1	1350	185	0.25																														E-133M
	← GAS 2 →	1	1350	185	0.25																														E-133M
	LODGING →	1	1350	185	0.25																														E-133M
	HOSPITAL 3 →	1	1350	185	0.25																														E-133M
ABIO+142.8, RT		1	450	600	0.27						1		X																				[SIGN ID CODE WI-8]		E-150M
ABIO+149.3, RT		1	450	600	0.27						1		X																				[SIGN ID CODE WI-8]		E-150M
ABIO+162.8, RT		1	450	600	0.27						1		X																				[SIGN ID CODE WI-8]		E-150M
ABIO+173.3, RT		1	450	600	0.27						1		X																				[SIGN ID CODE WI-8]		E-150M
ABIO+177.5, LT		1	900	900	0.81						2			X																				[SIGN ID CODE W3-3]		E-152M
ABIO+182.8, RT		1	450	600	0.27						1		X																				[SIGN ID CODE WI-8]		E-150M
ABIO+188.0, RT	BRIDGE AB-1 VT 9 / BRIDGE AB-1 VT 279	1	150	200	0.03						1	X																						[SIGN ID CODE VD-701]		E-134M
ABIO+194.0, LT	BRIDGE AB-1 VT 9 / BRIDGE AB-1 VT 279	1	150	200	0.03						1	X																						[SIGN ID CODE VD-701]		E-134M
												m 6.6	m 28.0	m 9.4	m	m	m		EA	kg	kg	kg		kg 85.9										
	TOTALS				m^2 4.91	m^2	EA.	m^2				m 44.0			m					kg	EA. 2	kg 85.9					EA.	EA.	kg						

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT: BENNINGTON - HOOSICK
PROJECT NO.: D.P.I. 0146(1) C/4

DESIGN FILE NAME:
IPARM FILE NAME: N/A
SURVEYED BY: N/A
SQUAD LEADER: T.P.K.
DWG. NO. TSS-5

PLOT DATE: 9/00
SURVEY DATE: N/A
DRAWN BY: K.H.D.
SHEET: 141 OF 385

FILE NAME =u:\5116\vaot\contract4\tss-1.dgn
DATE/TIME =26 SEP 2000
USER =1459