STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) 44 kg/m 2.8	50 kg/m 3.2	63 kg/m 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) 75 kg/m 1.9	100 kg/m 2.5	100 MOD kg/m 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	75 kg/m 11.3	89 kg/m 13.4	100 kg/m 16.1	125 kg/m 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	MASS	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
RAMP CD CD9+980.0, RT	ONLY	1	900	750	0.68						1			X																				[SIGN ID CODE VR-922]		E-145AM
CD9+980.1, ℄		1	600	750	0.45						1			X																				[SIGN ID CODE R4-7]		E-144M
		1 1	450 450	450 450	0.20 0.20																												[SIGN ID CODE OM-1] [SIGN ID CODE OM-1] BACK-TO-BACK		E-150M E-150M
CD9+984.7, LT	LEGAL LOAD LIMIT 24,000 POUNDS	1	600	750	0.45						1			X																				[SIGN ID CODE VR-017]		E-141M
	SPEED LIMIT 35	1	600	750	0.45																												[SIGN ID CODE R2-1]		E-142M
CD10+002.6, ℄		1	600	750	0.45						1			X																				[SIGN ID CODE R4-7]		E-144M
		1 1	450 450	450 450	0.20 0.20																												[SIGN ID CODE OM-1] [SIGN ID CODE OM-1] BACK-TO-BACK		E-150M E-150M
CD10+030.9, RT		1	450	450	0.20						1	X																						[SIGN ID CODE OM-1]		E-150M
CD10+030.9, RT		1	450	450	0.20						1	X																						[SIGN ID CODE OM-1]		E-150M
CD10+031.3, RT	EAST	1	600	300	0.18						1			X																				[SIGN ID CODE M3-2]		E-136BM
	VERMONT ~~9~~ 279	1	600	600	0.36																												[SIGN ID CODE MI-5]		E-136BM
		1	525	375	0.20																												[SIGN ID CODE M6-3]		E-136BM
CD10+038.3, RT	ONE WAY ONE WAY	1 1	900 900	300 300	0.27 0.27						1		X																				[SIGN ID CODE R6-1R] [SIGN ID CODE R6-1L] BACK-TO-BACK		E-142M E-142M
											m 6.6	m 3.6	m 23.7	m	m	m		EA	kg	kg	kg		kg	kg	kg	kg								
TOTALS			m² 4.96	m²	EA.	m²					m 33.9			m					kg	EA.	kg						EA.	EA.	kg							

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT: BENNINGTON - HOOSICK
PROJECT NO.: D.P.I. 0146(1) C/4
DESIGN FILE NAME:
IPARM FILE NAME: N/A
SURVEYED BY: N/A
SQUAD LEADER: T.P.K.
DWG. NO. TSS-8
PLOT DATE: 9/00
SURVEY DATE: N/A
DRAWN BY: K.H.D.
SHEET: 144 OF 385

FILE NAME =u:\5116\vaot\contract4\tss-1.dgn
DATE/TIME =07 SEP 2000
USER =1459