STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 2.8	50 3.2	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	MASS	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
VT. RTE 67A 60+890.0, LT	TO	1	600	300	0.18						2												2	X							X	[SIGN ID CODE M4-5]		E-136BM
	HISTORIC TO	1 1	600 600	300 300	0.18 0.18																											[SIGN ID CODE VM-078] [SIGN ID CODE M4-5]		E-136BM E-136AM
	VERMONT 7A 7	1 1	600 600	600 600	0.36 0.36																											[SIGN ID CODE MI-5] [SIGN ID CODE MI-4]		E-136BM E-136AM
	SOUTH EAST	1 1	600 600	300 300	0.18 0.18																											[SIGN ID CODE M3-3] [SIGN ID CODE M3-2]		E-136BM E-136BM
	VERMONT 67A VERMONT ~~9~~ 279	1 1	600 600	600 600	0.36 0.36																											[SIGN ID CODE MI-5] [SIGN ID CODE MI-5]		E-136BM E-136BM
		1 1	525 525	375 375	0.20 0.20																											[SIGN ID CODE M6-3] [SIGN ID CODE M6-1]		E-136BM E-136BM
60+900.0, RT	N. BENNINGTON 3	1	1800	250	0.45						2		X																			[SIGN ID CODE DI-1]	TSD-3	
	TROY NY 27~~33~~	1	1800	250	0.45																											[SIGN ID CODE DI-1]	TSD-3	
60+910.0, LT	BENNINGTON 1	1	1800	250	0.45						2		X																			[SIGN ID CODE DI-1]	TSD-3	
	MANCHESTER 24	1	1800	250	0.45																											[SIGN ID CODE DI-1]	TSD-3	
60+980.0, LT	TO	1	600	300	0.18						2												2	X							X	[SIGN ID CODE M4-5]		E-136BM
	HISTORIC TO	1 1	600 600	300 300	0.18 0.18																											[SIGN ID CODE VM-078] [SIGN ID CODE M4-5]		E-136BM E-136AM
	VERMONT 7A 7	1 1	600 600	600 600	0.36 0.36																											[SIGN ID CODE MI-5] [SIGN ID CODE MI-4]		E-136BM E-136AM
	SOUTH EAST	1 1	600 600	300 300	0.18 0.18																											[SIGN ID CODE M3-3] [SIGN ID CODE M3-2]		E-136BM E-136BM
	VERMONT 67A VERMONT ~~9~~ 279	1 1	600 600	600 600	0.36 0.36																											[SIGN ID CODE MI-5] [SIGN ID CODE MI-5]		E-136BM E-136BM
		1 1	525 525	375 375	0.20 0.20																											[SIGN ID CODE M6-3] [SIGN ID CODE M5-1R]		E-136BM E-136BM
											m 16.8	m	m	m	m	m	EA	kg	kg	kg		kg 194.4	kg	kg	kg	EA.	EA.	kg					
	TOTALS	m^2 7.28	m^2	EA.	m^2						m 16.8			m				kg	EA. 4	kg 194.4		EA.	EA.	kg								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT: BENNINGTON - HOOSICK
PROJECT NO.: D.P.I. 0146(1) C/4

DESIGN FILE NAME:
IPARM FILE NAME: N/A
SURVEYED BY: N/A
SQUAD LEADER: T.P.K.
DWG. NO. TSS-16

PLOT DATE: 9/00
SURVEY DATE: N/A
DRAWN BY: K.H.D.
SHEET: 152 OF 385

FILE NAME = u:\5116\vaot\contract4\tss-1.dgn
DATE/TIME = 07 SEP 2000
USER = 1459