STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 2.8	50 3.2	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	MASS	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
VT. RTE 67A 60+980.0, RT	TO	1	600	300	0.18						2												2	X								X	[SIGN ID CODE M4-5]		E-136BM
	NY	1	600	300	0.18																														TSD-2	
	7	1	600	600	0.36																													[SIGN ID CODE M5-1]	TSD-2	
	WEST NORTH	1 1	600 600	300 300	0.18 0.18																													[SIGN ID CODE M3-4] [SIGN ID CODE M3-1]		E-136BM E-136BM
	279 ~~9~~ VERMONT 67A	1 1	600 600	600 600	0.36 0.36																													[SIGN ID CODE M1-5] [SIGN ID CODE M1-5]		E-136BM E-136BM
		1 1	525 525	375 375	0.20 0.20																													[SIGN ID CODE M6-1] [SIGN ID CODE M6-3]		E-136BM E-136BM
61+010.0, LT	SPEED LIMIT 40	1	600	750	0.45						1			X																				[SIGN ID CODE R2-1]		E-142M
61+045.0, RT	ONLY ONLY	1	1500	750	1.13						2			X																				[SIGN ID CODE VR-94I]		E-145AM
61+048.1, LT	SOUTH	1	600	300	0.18						1			X																				[SIGN ID CODE M3-3]		E-136BM
	VERMONT 67A	1	600	600	0.36																													[SIGN ID CODE M1-5]		E-136BM
61+091.6, LT		1	600	750	0.45						1			X																				[SIGN ID CODE R4-7]		E-144M
		1 1	450 450	450 450	0.20 0.20																													[SIGN ID CODE OM-1] [SIGN ID CODE OM-1] BACK-TO-BACK		E-150M E-150M
61+133.5, RT		1	600	750	0.45						1			X																				[SIGN ID CODE R4-7]		E-144M
		1 1	450 450	450 450	0.20 0.20																													[SIGN ID CODE OM-1] [SIGN ID CODE OM-1] BACK-TO-BACK		E-150M E-150M
												m	m	m 25.2	m	m	m		EA	kg	kg	kg		kg 94.9	kg	kg	kg								
	TOTALS		m^2 6.02	m^2	EA.	m^2						m 25.2			m					kg			EA. 2	kg 94.9				EA.	EA.	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT:	PROJECT NO.:
BENNINGTON - HOOSICK	D.P.I. 0146(1) C/4
DESIGN FILE NAME:	
IPARM FILE NAME: N/A	PLOT DATE: 9/00
SURVEYED BY: N/A	SURVEY DATE: N/A
SQUAD LEADER: T.P.K.	DRAWN BY: K.H.D.
DWG. NO. TSS-17	SHEET: 153 OF 385

FILE NAME = u:\511GV\aot\contract4\tss-1.dgn
DATE/TIME = 27 SEP 2000
USER = 1459