STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 2.8	50 3.2	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	MASS	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
VT. RTE 67A 61+244.1, RT	↑ N. BENNINGTON 3	1	1800	250	0.45						2		X																				[SIGN ID CODE D1-1]	TSD-3	
61+245.0, LT	↑ BENNINGTON 1	1	1800	250	0.45						2		X																				[SIGN ID CODE D1-1]	TSD-3	
	TROY NY 27 ~~33~~ →	1	1800	250	0.45																												[SIGN ID CODE D1-1]	TSD-3	
61+305.0, LT	JCT	1	525	375	0.20						1			X																				[SIGN ID CODE M2-1]		E-136BM
	VERMONT ~~9~~ 279	1	600	600	0.36																												[SIGN ID CODE M1-5]		E-136BM
	SHEET SUBTOTAL				1.91	-	-					-	17.2	4.3									-	-					-	-	-				
	DWG. NO. TSS-1 SUBTOTAL				1.41	-	-					3.3	-	11.8									-	-					-	-	-				
	DWG. NO. TSS-2 SUBTOTAL				6.88	23.10	-					-	3.6	60.1									-	-					-	-	-				
	DWG. NO. TSS-3 SUBTOTAL				4.94	-	-					5.0	3.6	25.6									-	-					-	-	-				
	DWG. NO. TSS-4 SUBTOTAL				7.89	-	-					3.2	-	30.7									2	104.0					-	-	-				
	DWG. NO. TSS-5 SUBTOTAL				4.91	-	-					6.6	28.0	9.4									2	85.9					-	-	-				
	DWG. NO. TSS-6 SUBTOTAL				3.63	-	-					3.3	16.0	25.0									-	-					-	-	-				
	DWG. NO. TSS-7 SUBTOTAL				3.92	49.88	-					3.3	24.0	27.1									2	97.2					-	-	-				
	DWG. NO. TSS-8 SUBTOTAL				4.96	-	-					6.6	3.6	23.7									-	-					-	-	-				
	DWG. NO. TSS-9 SUBTOTAL				7.89	-	-					3.2	-	17.9									3	154.0					-	-	-				
	DWG. NO. TSS-10 SUBTOTAL				3.83	-	-					-	-	9.2									2	85.9					-	-	-				
	DWG. NO. TSS-11 SUBTOTAL				3.55	-	-					-	20.0	-									2	104.0					-	-	-				
	DWG. NO. TSS-12 SUBTOTAL				2.49	37.98	-					3.3	4.0	19.8									2	97.2					-	-	-				
	DWG. NO. TSS-13 SUBTOTAL				2.01	-	-					3.3	24.0	4.0									-	-					-	-	-				
	DWG. NO. TSS-14 SUBTOTAL				6.81	-	-					-	8.2	12.5									3	149.2					-	-	-				
	DWG. NO. TSS-15 SUBTOTAL				4.73	-	-					4.0	-	25.2									-	-					-	-	-				
	DWG. NO. TSS-16 SUBTOTAL				7.28	-	-					-	16.8	-									4	194.4					-	-	-				
	DWG. NO. TSS-17 SUBTOTAL				6.02	-	-					-	-	25.2									2	94.9					-	-	-				
	DWG. NO. TSS-18 SUBTOTAL				5.22	-	-					3.0	-	16.8									2	97.2					-	-	-				
					m 48.1	m 169.0	m 348.3		m	m	m		EA	kg	kg	kg		kg 1263.9	kg	kg	kg														
	TOTALS				m^2 90.28	m^2 110.96	EA.	m^2			m 565.4				m						kg		EA. 26	kg 1263.9					EA.	EA.	kg				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT:	PROJECT NO.:
BENNINGTON - HOOSICK	D.P.I. 0146(1) C/4
DESIGN FILE NAME:	
IPARM FILE NAME: N/A	PLOT DATE: 9/00
SURVEYED BY: N/A	SURVEY DATE: N/A
SQUAD LEADER: T.P.K.	DRAWN BY: K.H.D.
DWG. NO. TSS-19	SHEET: 155 OF 385

FILE NAME =u:\516\vaot\contract4\tss-1.dgn
DATE/TIME =07 SEP 2000
USER =1459