STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75	2.0	2.5	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0	4.0	4.0 MOD	FOUNDATION	TUBULAR STEEL Ø (in) lb/ft 3.0	3.5	4.0	5.0	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
														OPTION ITEMS																							
HISTORIC VT. ROUTE 7A: 134+99.0, LT	PROSPECT ST						1				1			X 13'		X		X																SALVAGED SIGN TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGN ON NEW POST, COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.	-	-
	STOP 0071 0206 0256	1	30	30	6.25																												BACK-TO-BACK		E-143
		1	6	10	0.42																												SIGN ID CODE RI-1 SIGN ID CODE VD-700		E-138
170+01.0, RT	RIVER RD MAIN ST						1 1				1			X 13'		X		X																SALVAGED SIGNS TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGN ON NEW POST, COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.	- -	- -
	STOP 0071 0206 0322	1	30	30	6.25																												BACK-TO-BACK		E-143
		1	6	10	0.42																												SIGN ID CODE RI-1 SIGN ID CODE VD-700		E-138
172+67.0, LT	TACONIC RD						1				1			X 13'		X		X																SALVAGED SIGN TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGN ON NEW POST, COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.	-	-
	STOP 0071 0206 0327	1	30	30	6.25																												BACK-TO-BACK		E-143
		1	6	10	0.42																												SIGN ID CODE RI-1 SIGN ID CODE VD-700		E-138
187+50.0, RT		1	30	30	6.25						1			X 15'		X		X																SIGN ID CODE WI1-2 SIGN SHALL HAVE A FLUORESCENT YELLOW GREEN BACKGROUND.		E-152
		1	24	12	2.00																												SIGN ID CODE WI6-7P SIGN SHALL HAVE A FLUORESCENT YELLOW GREEN BACKGROUND.		E-152
188+85.0, LT		1	30	30	6.25						1			X 15'		X		X																SIGN ID CODE WI1-2 SIGN SHALL HAVE A FLUORESCENT YELLOW GREEN BACKGROUND.		E-152
		1	24	12	2.00																												SIGN ID CODE WI6-7P SIGN SHALL HAVE A FLUORESCENT YELLOW GREEN BACKGROUND.		E-152
188+95.0, RT	MAIN ST UNION ST						1 1				1			X 13'		X		X																SALVAGED SIGNS TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGN ON NEW POST, COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.	- -	- -
	STOP 0071 0206 0357	1	30	30	6.25																												BACK-TO-BACK		E-143
		1	6	10	0.42																												SIGN ID CODE RI-1 SIGN ID CODE VD-700		E-138
												LF	LF	LF 82.0 ~~84.0~~	LF	LF 84.0	LF		EA.	LB	LB	LB		LB	LB	LB	LB								
TOTALS		SF 43.18	SF	EA. 6	SF							LF ~~84.0~~ 82.0			LF 84.0					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC OPERATIONS SECTION "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #1

PROJECT NAME: MANCHESTER
PROJECT NUMBER: STP 2203(I)S

FILE NAME: tss.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.M.
IPARM FILE: p99c158tss01.i

PLOT DATE: 09-MAY-2008
DRAWN BY: C.A.K.
CHECKED BY: D.W.E.
SHEET 47 OF 68