STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 10

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (In)	HEIGHT (In)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (In) 1.75 lb/ft 1.88	2.0 lb/ft 2.16	2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (In) 3.0 lb/ft 1.3	4.0 lb/ft 1.7	4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (In) FOUND-ATION	3.0 lb/ft 7.6	3.5 lb/ft 9.0	4.0 lb/ft 10.8	5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																									
HISTORIC VT. ROUTE 7A: 266+05.0, LT		1	30	30	6.25						1			X 15'		X		X																	SIGN ID CODE W11-2 SIGN SHALL HAVE A FLUORESCENT YELLOW GREEN BACKGROUND.		E-152
		1	24	12	2.00																														SIGN ID CODE W16-7P SIGN SHALL HAVE A FLUORESCENT YELLOW GREEN BACKGROUND.		E-152
267+05.0, RT		1 1	36 36	12 12	3.00 3.00						2			12' X 12'																					BACK-TO-BACK SIGN ID CODE R6-1R SIGN ID CODE R6-1L		E-142 E-142
269+04.0, RT		1	24	30	5.00						1			X 13'		X		X																	SIGN ID CODE VR-017		E-141
270+18.0, RT							1 1				1			X 13'		X		X																	SALVAGED SIGNS TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGN ON NEW POST, COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.	- -	- -
		1 1	30 6	30 10	6.25 0.42																													BACK-TO-BACK SIGN ID CODE R1-1 SIGN ID CODE VD-700		E-143 E-138
276+55.0, RT							1 1				1			X 13'		X		X																	SALVAGED SIGNS TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGN ON NEW POST, COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.	- -	- -
		1 1	30 6	30 10	6.25 0.42																													BACK-TO-BACK SIGN ID CODE R1-1 SIGN ID CODE VD-700		E-143 E-138
281+70.0, RT		1	24	30	5.00						1			X 13'		X		X																	SIGN ID CODE VR-017		E-141
												LF	LF	LF ~~70.0~~ (28.0)	LF	LF 70.0	LF		EA.	LB	LB	LB		LB	LB	LB	LB							
	TOTALS	SF 37.59	SF	EA. 4	SF							LF ~~70.0~~ (28.0)		91.0	LF 70.0					LB			EA.	LB				EA.	EA.	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC OPERATIONS SECTION "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #10

PROJECT NAME: MANCHESTER
PROJECT NUMBER: STP 2203(I)S

FILE NAME: tss.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.M.
IPARM FILE: p99cl58tssl0.i

PLOT DATE: 09-MAY-2008
DRAWN BY: C.A.K.
CHECKED BY: D.W.E.
SHEET 56 OF 68