STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 11

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.0 lb/ft 2.16	SQUARE STEEL (in) 2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	TUBULAR ALUMINUM Ø (in) 4.0 lb/ft 1.7	TUBULAR ALUMINUM Ø (in) 4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUND-ATION	TUBULAR STEEL Ø (in) 3.0 lb/ft 7.6	TUBULAR STEEL Ø (in) 3.5 lb/ft 9.0	TUBULAR STEEL Ø (in) 4.0 lb/ft 10.8	TUBULAR STEEL Ø (in) 5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON DWG. NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS																							
HISTORIC VT. ROUTE 7A: 281+91.0, RT	MAIN ST / BARNUMVILLE RD						1 1				1			X 13'		X		X															SALVAGED SIGNS TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGN ON NEW POST, COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.	- -	- -
	STOP 0071 0206 0533	1 1	30 6	30 10	6.25 0.42																												BACK-TO-BACK SIGN ID CODE R1-1 SIGN ID CODE VD-700		E-143 E-138
VT. ROUTE 11: 1+75.0, RT	ONLY ONLY	1	36	30	7.50						2			X 13'																			SIGN ID CODE VR-925 SIGN SHALL BE MOUNTED ON TWO FLANGED CHANNEL SIGN POSTS		E-145A
2+04.0, RT	BEGIN	1	24	12	2.00						1			X 15'		X		X															SIGN ID CODE M4-11		E-140
	CENTER LANE ONLY	1	24	36	6.00																												SIGN ID CODE R3-9B		E-140
2+04.0, LT	END	1	24	12	2.00						1			X 15'		X		X															SIGN ID CODE M4-6		E-140
	CENTER LANE ONLY	1	24	36	6.00																												SIGN ID CODE R3-9B		E-140
4+20.0, RT	LOCAL BUS / LOCAL BUS						1 1				1			X 12'		X		X															BACK-TO-BACK SALVAGED SIGN TO BE MOUNTED ON NEW POST SALVAGED SIGN TO BE MOUNTED ON NEW POST	- -	- -
4+53.0, RT		1	30	30	6.25						1			X 15'		X		X															SIGN ID CODE W11-2 SIGN SHALL HAVE A FLUORESCENT YELLOW GREEN BACKGROUND.		E-152
		1	24	12	2.00																												SIGN ID CODE W16-7P SIGN SHALL HAVE A FLUORESCENT YELLOW GREEN BACKGROUND.		E-152
												LF	LF	LF ~~70.0~~ (28.0)	LF	LF 70.0	LF		EA.	LB	LB	LB		LB	LB	LB	LB								
	TOTALS		SF 38.42	SF	EA. 4	SF						LF ~~70.0~~ (28.0) 83.0			LF 70.0					LB			EA.	LB				EA.	EA.	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC OPERATIONS SECTION "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #11

PROJECT NAME: MANCHESTER
PROJECT NUMBER: STP 2203(I)S

FILE NAME: tss.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.M.
IPARM FILE: p99c158tssll.i

PLOT DATE: 09-MAY-2008
DRAWN BY: C.A.K.
CHECKED BY: D.W.E.
SHEET 57 OF 68