STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 12

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (In)	HEIGHT (In)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.16	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUNDATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																									
VT. ROUTE II: 4+62.0, LT		1	30	30	6.25						1			X 15′		X		X															SIGN ID CODE W11-2 SIGN SHALL HAVE A FLUORESCENT YELLOW GREEN BACKGROUND.		E-152
		1	24	12	2.00																												SIGN ID CODE W16-7P SIGN SHALL HAVE A FLUORESCENT YELLOW GREEN BACKGROUND.		E-152
4+84.0, RT	COTTAGE ST DEPOT ST						1 1				1			X 13′		X		X															SALVAGED SIGNS TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGN ON NEW POST, COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.	- -	- -
	STOP 0110 0206 0009	1 1	30 6	30 10	6.25 0.42																												BACK-TO-BACK SIGN ID CODE RI-1 SIGN ID CODE VD-700		E-143 E-138
6+80.0, RT		1	24	36	6.00						1			X 14′		X		X															SIGN ID CODE R3-9B		E-140
9+52.0, LT		1	24	36	6.00						1			X 14′		X		X															SIGN ID CODE R3-9B		E-140
11+70.0, RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1			X 13′		X		X															SIGN ID CODE VR-017		E-141
12+22.0, RT	DEPOT ST RIVERSIDE HEIGHTS	1					1 1				1			X 13′		X		X															SALVAGED SIGNS TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGN ON NEW POST, COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.	- -	- -
	STOP 0110 0206 0023	1 1	30 6	30 10	6.25 0.42																												BACK-TO-BACK SIGN ID CODE RI-1 SIGN ID CODE VD-700		E-143 E-138
14+35.0, LT	LOCAL BUS LOCAL BUS						1 1				1			X 12′		X		X															BACK-TO-BACK SALVAGED SIGNS TO BE MOUNTED ON NEW POST	- -	- -
												LF	LF	LF ~~98.0~~ 94.0	LF	LF 98.0	LF		EA.	LB	LB	LB		LB	LB	LB	LB								
TOTALS		SF 38.59	SF	EA. 6	SF							LF ~~98.0~~ 94.0			LF 98.0					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC OPERATIONS SECTION "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #12

PROJECT NAME: MANCHESTER
PROJECT NUMBER: STP 2203(I)S

FILE NAME: tss.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.M.
IPARM FILE: p99cl58tssl2.i
PLOT DATE: 09-MAY-2008
DRAWN BY: C.A.K.
CHECKED BY: D.W.E.
SHEET 58 OF 68