STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES												TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
									ROADWAY	ROADWAY (NO FED/ STATE PART)	BRIDGE NO. 75	FULL C.E.	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITY	UNIT	ITEMS
									65				65		CY	STONE FILL, TYPE II	613.11	EST			
									275				275		LF	VERTICAL GRANITE CURB	616.21	3.7			
									1010				1010		LF	BITUMINOUS CONCRETE CURB, TYPE A	616.305	II			
									35				35		LF	REMOVING AND RESETTING CURB	616.40	1			
									10				10		TON	BITUMINOUS CONCRETE GUTTERS AND TRAFFIC ISLANDS	616.47	1			
									85				85		SY	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	618.10	1.2			
									35				35		SY	PORTLAND CEMENT CONCRETE SIDEWALK, 8 INCH	618.11	4.9			
									150				150		SF	DETECTABLE WARNING SURFACE	618.30	12			
									20				20		EACH	YIELDING MARKER POSTS	619.17	-			
									525				525		LF	SNOW BARRIER, GALVANIZED	620.75	5			
									3650				3650		LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20	11			
									1210				1210		LF	STEEL BEAM GUARDRAIL, GALVANIZED W/8 FEET POSTS	621.205	8.5			
									120				120		LF	HD STEEL BEAM GUARDRAIL, GALVANIZED	621.21	7.25			
									9				9		EACH	MANUFACTURED TERMINAL SECTION, FLARED	621.50	-			
									24				24		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60	-			
									45				45		EACH	REPLACE GUARDRAIL POST ASSEMBLY	621.76	3			
									25				25		EACH	REPLACE GUARDRAIL BEAM UNIT	621.77	4			
									4975				4975		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	34			
									2				2		EACH	REMOVAL AND DISPOSAL OF GUIDE POSTS	621.81	-			
										38			38		EACH	ADJUST ELEVATION OF VALVE BOX	629.20	EST			
									1180				1180		HR	UNIFORMED TRAFFIC OFFICERS	630.10	-			
									3540				3540		HR	FLAGGERS	630.15	-			
												0.46	0.46		LS	FIELD OFFICE, ENGINEERS	631.10	-			
												0.10	0.10		LS	TESTING EQUIPMENT, CONCRETE	631.16	-			
												0.46	0.46		LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-			
												0.46	0.46		LU	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.25	-			
									0.46				0.46		LS	MOBILIZATION/DEMOBILIZATION	635.11	-			
									1				1		LS	TRAFFIC CONTROL (STP 2206 (I)S)	641.10	-			
									0.5				0.5		LS	PUBLIC RELATIONS OFFICER	641.12	-			
									2				2		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-			
									46300				46300		LF	DURABLE 4 INCH WHITE LINE, THERMOPLASTIC	646.402	65			
									47750				47750		LF	DURABLE 4 INCH YELLOW LINE, THERMOPLASTIC	646.412	50			
									700				700		LF	DURABLE 8 INCH YELLOW LINE, THERMOPLASTIC	646.452	9			
									575				575		LF	DURABLE 24 INCH STOP BAR, THERMOPLASTIC	646.482	5			
									179				179		EACH	DURABLE LETTER OR SYMBOL, THERMOPLASTIC	646.492	-			

PROJECT NAME: HARTFORD - NORWICH
PROJECT NUMBER: STP 2206(I)S

FILE NAME: /pave/99c164/pc164
PROJECT LEADER: PTS
DESIGNED BY: NLL
IPARM FILE NAME: pc164qs02.i

PLOT DATE: 14-FEB-2012 15:49
DRAWN BY: MRS
CHECKED BY: PTS
SHEET 20 OF 137