STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET #2

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) lb/ft 1.75	SQUARE STEEL (in) lb/ft 2.0	SQUARE STEEL (in) lb/ft 2.5	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0	TUBULAR ALUMINUM Ø (in) lb/ft 4.0	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 MOD	TUBULAR STEEL Ø (in) FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0	TUBULAR STEEL Ø (in) lb/ft 3.5	TUBULAR STEEL Ø (in) lb/ft 4.0	TUBULAR STEEL Ø (in) lb/ft 5.0	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS																								
261+54 RT							1				1					X		X																		
							1 1																										BACK TO BACK		
278+94 LT	BUS STOP						1				1	13.50				X		X																		
279+17 LT	CHANDLER RD						1				1					X		X															SIGN TO BE MOUNTED PERPENDICULAR TO TOP OF STOP SIGN.		
	HARTFORD AVE						1																										SIGN TO BE MOUNTED PERPENDICULAR TO TOP OF STOP SIGN.		
	STOP 0050 1408 0529	1 1	30 6	30 10	6.25 0.42																												R1-1 BACK TO BACK		E-143 E-138
279+98 RT	LEGAL LOAD LIMIT 24,000 POUNDS						1				1					X		X																		
	SPEED LIMIT 25						1																													
280+48 RT	FROST PARK						1				1					X		X															SIGN TO BE MOUNTED PERPENDICULAR TO TOP OF STOP SIGN.		
	A STREET						1																										SIGN TO BE MOUNTED PERPENDICULAR TO TOP OF STOP SIGN.		
	STOP 0050 1408 0530						1 1																										BACK TO BACK		
280+53 RT	BUS STOP						1				1					X		X																		
288+72 RT	STOP 0050 1408 0547	1 1	30 6	30 10	6.25 0.42				1																								R1-1 BACK TO BACK		E-143 E-138
												FT	FT	FT	FT	FT 90.0	FT		EA	LB	LB	LB		LB	LB	LB	LB								
SHEET TOTALS					SF 13.34	SF	EA. 13	EA.				FT 81.75 LF			FT 90.0					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND VTRANS "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #2

PROJECT NAME: HARTFORD-NORWICH
PROJECT NUMBER: STP 2206(1)S

FILE NAME: /pave/99c164/pc164
PROJECT LEADER: PTS
DESIGNED BY: NLL
IPARM FILE NAME: pc164tss02.i

PLOT DATE: 14-FEB-2012 15:52
DRAWN BY: MRS
CHECKED BY: NLL
SHEET 71 OF 137