

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
								ROADWAY	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
								9			9		EACH	THINNING AND TRIMMING FOR SIGNS	201.31	-			
								100			100		CY	COMMON EXCAVATION	203.15	EST			COLD PLANING, BITUMINOUS CONCRETE
								2			2		CY	SOLID ROCK EXCAVATION	203.16	0.5	85157.57	SY	VT ROUTE 14
								425			425		CY	EARTH BORROW	203.30	-	42.43	SY	ROUNDING
								3			3		CY	TRENCH EXCAVATION OF EARTH	204.20	0.1	85200	SY	TOTAL
								1			1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	EST			SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (PG 58-34)
								85200			85200		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	42.43			WEARING COURSE
								525			525		TON	AGGREGATE SHOULDERS, RAP	402.13	24	6978.92	TON	TYPE IVS
								365			365		CWT	EMULSIFIED ASPHALT	404.65	4.87			SIDERoads, DRIVES, AND PULL-OFFS
								1			1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-	336.68	TON	TYPE IVS
								9800			9800		TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (PG 58-34)	490.30	158.09			LEVELING COURSE
								1			1		LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-	2326.31	TON	TYPE VS
									75		75		LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10	3			ROUNDING
									213		213		LF	REMOVAL OF EXISTING RAILING	525.10	-	158.09	TON	TOTAL
								105			105		LF	15" CPEP	601.0910	5	9800	TON	
								4			4		LF	RE-LAYING PIPE CULVERTS (15")	601.99	-			AGGREGATE SHOULDERS, RAP
								2			2		CY	CEMENT MASONRY	602.15	0.7			USED ALONG SHOULDERS
								3			3		EACH	CHANGING ELEVATION OF DROP INLETS, CATCH BASINS, OR MANHOLES	604.40	-	187.50	TON	USED AT MANUFACTURED TERMINAL SECTIONS
								89			89		EACH	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS I	604.412	-	85.00	TON	USED AT GRAVEL TURNOUTS
								3			3		EACH	CHANGING ELEVATION OF SEWER MANHOLES	604.42	-	228.50	TON	ROUNDING
								125			125		HR	POWER GRADER RENTAL	608.15	EST	24.00	TON	TOTAL
								345			345		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST	525	TON	
								80			80		HR	POWER BROOM RENTAL, TYPE I	608.30	EST			
								40			40		HR	POWER BROOM RENTAL, TYPE II	608.31	EST			
								700			700		HR	TRUCK RENTAL	608.37	EST			
								125			125		HR	LOADER RENTAL, TYPE I	608.40	EST			
								410			410		CY	STONE FILL, TYPE I	613.10	10			
								90			90		TON	BITUMINOUS CONCRETE GUTTERS AND TRAFFIC ISLANDS	616.47	1.2			
								4			4		EACH	RELOCATE MAILBOX, SINGLE SUPPORT	617.10	-			
								9			9		SY	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	618.10	-			
								95			95		EACH	YIELDING MARKER POSTS	619.17	2			
								8811			8811		LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20	-			
								400			400		LF	STEEL BEAM GUARDRAIL, GALVANIZED W/8 FEET POSTS	621.205	-			
								450			450		LF	HD STEEL BEAM GUARDRAIL, GALVANIZED	621.21	-			
								17			17		EACH	MANUFACTURED TERMINAL SECTION, FLARED	621.50	-			
								32			32		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60	-			
								10022			10022		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	-			
								500			500		HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST			
								3000			3000		HR	FLAGGERS	630.15	EST			
										1	1		LS	FIELD OFFICE, ENGINEERS	631.10	-			

PROJECT NAME: WILLIAMSTOWN-BARRE TOWN
PROJECT NUMBER: STP 2210 (1)S

FILE NAME: p99c172.dgn
PROJECT MANAGER: EPD
DESIGNED BY: CDL
QUANTITY SHEET #1

PLOT DATE: 10/26/2007
DRAWN BY: RHB
CHECKED BY: EPD
SHEET 8 OF 32