STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 4

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (In)	HEIGHT (In)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.0 lb/ft 2.16	SQUARE STEEL (in) 2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	TUBULAR ALUMINUM Ø (in) 4.0 lb/ft 1.7	TUBULAR ALUMINUM Ø (in) 4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUNDATION	TUBULAR STEEL Ø (in) 3.0 lb/ft 7.6	TUBULAR STEEL Ø (in) 3.5 lb/ft 9.0	TUBULAR STEEL Ø (in) 4.0 lb/ft 10.8	TUBULAR STEEL Ø (in) 5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
														OPTION ITEMS																							
STA. 285+30 RT	STOP BROCKWAY HILL RD	1	30	30	6.25		1																										RI-1 MOUNT STREET SIGN OVER STOP SIGN. POST TOP MOUNTING BRACKET REQUIRED FOR FLANGED CHANNEL POST OPTION.		E-143
	0140 0917 0540	1	6	10	0.42						1			X		X																MOUNT REF. PLAQUE BACK TO BACK WITH STOP SIGN.		E-138
STA. 305+26 LT	STOP FALLS BRIDGE RD	1	30	30	6.25		1																										RI-1 MOUNT STREET SIGN OVER STOP SIGN. POST TOP MOUNTING BRACKET REQUIRED FOR FLANGED CHANNEL POST OPTION.		E-143
	0140 0917 0578	1	6	10	0.42						1			X		X																MOUNT REF. PLAQUE BACK TO BACK WITH STOP SIGN.		E-138
STA. 305+77 LT	LEGAL LOAD LIMIT 24,000 POUNDS; SPEED LIMIT 35	1	24	30	5.00		1				1			X		X																VR-017 MOUNT SPEED LIMIT SIGN BELOW LEGAL LOAD LIMIT		E-141
STA. 321+74 RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1			X		X																VR-017		E-141
STA. 322+04 RT	STOP HULBERT RD	1	30	30	6.25		1																										RI-1 MOUNT STREET SIGN OVER STOP SIGN. POST TOP MOUNTING BRACKET REQUIRED FOR FLANGED CHANNEL POST OPTION.		E-143
	0140 0917 0610	1	6	10	0.42						1			X		X																MOUNT REF. PLAQUE BACK TO BACK WITH STOP SIGN.		E-138
STA. 339+24 RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1			X		X																VR-017		E-141
STA. 339+51 RT	STOP FARNHAM RD	1	30	30	6.25		1																										RI-1 MOUNT STREET SIGN OVER STOP SIGN. POST TOP MOUNTING BRACKET REQUIRED FOR FLANGED CHANNEL POST OPTION.		E-143
	0140 0917 0644	1	6	10	0.42						1			X		X																MOUNT REF. PLAQUE BACK TO BACK WITH STOP SIGN.		E-138
STA. 353+82 RT	STOP	1	30	30	6.25						1			X		X																RI-1		E-143
BARRE STA. 1+90 RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1			X		X																VR-017		E-141
STA. 2+15 RT	STOP KINGS ROW	1	30	30	6.25		1																										RI-1 MOUNT STREET SIGN OVER STOP SIGN. POST TOP MOUNTING BRACKET REQUIRED FOR FLANGED CHANNEL POST OPTION.		E-143
	0140 0917 0004	1	6	10	0.42						1			X		X																MOUNT REF. PLAQUE BACK TO BACK WITH STOP SIGN.		E-138
					SF 59.60	SF	EA. 6	SF				FT 150	FT	FT 150	FT	FT 150	FT		EA	LB	LB	LB	EA.	LB	LB	LB	LB	EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE ROADWAY, TRAFFIC & SAFETY SECTIONS "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET 4

PROJECT NAME: WILLIAMSTOWN-BARRE TOWN
PROJECT NUMBER: STP 2210 (1)S

FILE NAME: p99c172.dgn
PROJECT LEADER: EPD
DESIGNED BY: CDL
PLOT FILE: p99c172+ss4.1

PLOT DATE: 29-APR-2009 13:3
DRAWN BY: RHB
CHECKED BY: EPD
SHEET 29 OF 32