STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) lb/ft 1.75 / 1.88	SQUARE STEEL (in) lb/ft 2.0 / 2.16	SQUARE STEEL (in) lb/ft 2.5 / 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 / 1.3	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 / 1.7	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 MOD. / 1.7	FOUNDATION	TUBULAR STEEL Ø (in) lb/ft 3.0 / 7.6	TUBULAR STEEL Ø (in) lb/ft 3.5 / 9.0	TUBULAR STEEL Ø (in) lb/ft 4.0 / 10.8	TUBULAR STEEL Ø (in) lb/ft 5.0 / 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
														OPTION ITEMS																								
175+85 LT	STOP 1003 0806 0331	1	30	30	6.25		1				1			14 X		X																				BACK TO BACK		E-143
176+40 LT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.0						1			16 X		X																				REFER TO STANDARD E-121 FOR PLACEMENT.		E-141
	SPEED LIMIT 35						1																													MOUNT EXISTING SIGN WITH NEW LEGAL LOAD LIMIT.		
233+00 RT	DEAD END						1				1			13 X		X																						
HYDE PARK 3+65 RT	1000 0805 0514 / 1003 0805 0009	2	6	10	0.84																														REPLACE EXISTING MILEMARKERS, MOUNT BACK-TO-BACK TO EACH OTHER ON EXISTING STOP SIGN.		E-138

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

	SF	SF	EA.	SF	LF	LF	LF	LF	LF	LF	EA.	LB	LB	LB	EA.	LB	LB	LB	LB	EA.	EA.	LB
SHEET TOTALS	12.09		3				~~45~~		~~45~~													
							43															
	35.25						128															
SIGN SHEET #1	~~29.0~~		3				~~165~~		~~165~~													
SIGN SHEET #2	12.09		3				~~45~~		~~45~~													
PROJECT TOTALS	47.34 ~~41.09~~		6		171 ~~210~~		43		~~210~~													

TRAFFIC SIGN SUMMARY SHEET #2

PROJECT: **JOHNSON - HYDE PARK**
PROJECT NO.: **STP 2215(1)S**
DATE: 7-07

DESIGN FILE NAME: p99c182.dgn
IPARM FILE NAME: p99c182ts2.i
SURVEYED BY:
SQUAD LEADER:

PLOT DATE: 08-JAN-2009 08:5
SURVEY DATE:
DRAWN BY: C.E.A., INC.
SHEET: **27** OF **33**