QUANTITY SHEET 1

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

			FULL E&C	EROSION CONTROL	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
						775	775	CY	EARTH BORROW	203.30	-
						1	1	CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	EST.
						9,000	9,000	SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	28.1
						850	850	TON	SUBBASE OF CRUSHED GRAVEL, FINE GRADED	301.28	EST.
						4,600	4,600	TON	AGGREGATE SHOULDERS	402.12	-
						970	970	CWT	EMULSIFIED ASPHALT	404.65	4.5
						1	1	LU	PRICE ADJUSTMENT ASPHALT CEMENT (N.A.B.I.)	406.50	-
									BEGIN OPTION AA		
						35,000	35,000	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (0% RAP CONTENT)	490.30	246
						35,000	35,000	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (0% < RAP CONTENT < 15.0%)	490.30	246
						35,000	35,000	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (15.0% <= RAP CONTENT < 25.0%)	490.30	246
						35,000	35,000	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (25.0% <= RAP CONTENT <= 50.0%)	490.30	246
									END OPTION AA		
						1	1	LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-
						1	1	LU	MAT. DENSITY PAY ADJUSTMENT (N.A.B.I.)	490.32	-
						1	1	LU	SURFACE TOLERANCE PAY ADJUSTMENT (N.A.B.I.)	490.33	-
						1	1	LU	LONGITUDINAL JOINT COMPACTION PAY ADJUSTMENT (N.A.B.I.)	490.34	-
					90		90	LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10	-
					100		100	CF	RAPID SETTING CONC. REPAIR MAT. W/ COARSE AGG.	580.20	EST.
						3	3	EA	REHAB DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS I	604.412	-
						2	2	EA	REHAB DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS II	604.415	-
						2	2	EA	REHAB DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS III	604.418	-
						1	1	EA	CHANGING ELEVATION OF SEWER MANHOLES	604.42	EST.
						400	400	HR	POWER GRADER RENTAL	608.15	EST.
						450	450	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.
						180	180	HR	POWER BROOM RENTAL, TYPE I	608.30	EST.
						180	180	HR	POWER BROOM RENTAL, TYPE II	608.31	EST.
						450	450	HR	TRUCK RENTAL	608.37	EST.
						120	120	HR	LOADER RENTAL, TYPE I	608.40	EST.
				1,210			1,210	CY	STONE FILL, TYPE I	613.10	27
						250	250	LF	TREATED TIMBER CURB	616.35	-
						1	1	EA	RELOCATE MAILBOX, SINGLE SUPPORT	617.10	-
						75	75	EA	YIELDING MARKER POSTS	619.17	EST.
						160	160	LF	SNOW BARRIER, GALVANIZED	620.75	EST.

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		COLD PLANING - BITUMINOUS PAVEMENT
1,555	SY	MAINLINE - APPROACHES
7,290.3	SY	MAINLINE - S.A.S.H. INTERSECTION
126.6	SY	SIDE ROADS
28.1	SY	ROUNDING
9,000	SY	TOTAL
		SUPERPAVE BITUMINOUS CONCRETE PAVEMENT
20,768	TON	MAINLINE (WEARING COURSE)
82	TON	SIDE ROADS (WEARING COURSE)
13,850	TON	MAINLINE (LEVELING COURSE)
54	TON	SIDE ROADS (LEVELING COURSE)
246	TON	ROUNDING
35,000	TON	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: FAIRFAX - ST. ALBANS TOWN
PROJECT NUMBER: STP 2217(1)

FILE NAME: p99c186.dgn
PROJECT LEADER: T. DOMEY
DESIGNED BY: K. LOCKE
PLOT FILE: p99c186qsl.i

PLOT DATE: 11-OCT-2011 11:48
DRAWN BY: K. LOCKE
CHECKED BY: PAVT MGMT
SHEET 6 OF 25