STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET

VAOT Metric

SUMMARY OF ESTIMATED QUANTITIES

				NON GOVT PARTICIPATING	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NUMBER	RND
						1080	1080	CM	EARTH BORROW	203.30	
						1	1	CM	TRENCH EXCAVATION OF EARTH (MOD. - EXPLORATORY) (N.A.B.I.)	204.20	
						19,618.5	19,618.5				
						~~16,650~~	~~16,650~~	SM	COLD PLANING - BITUMINOUS PAVEMENT	210.10	~~19~~
						985	985	T	AGGREGATE SHOULDERS	402.12	
						2195	2195	T	AGGREGATE SHOULDERS (MOD.)	402.12	
						22,932	22,932	KG	EMULSIFIED ASPHALT	404.65	
						14,000	14,000	T	MEDIUM DUTY BITUMINOUS CONCRETE PAVEMENT (PG 58-34)	406.27	
						1	1	LU	PRICE ADJUSTMENT ASPHALT CEMENT (N.A.B.I.)	406.50	
					10		~~10~~ 11	M	BRIDGE EXPANSION JOINT (ASPHALTIC PLUG TYPE)	516.10	1.8
					35		35	M	BRIDGE RAIL - H.D. STEEL BEAM/FASCIA MOUNTED (MOD. I)	525.41	
						~~22~~ 23	~~22~~ 23	EA	REHABING D.I., C.B., OR M.H., CLASS I	604.412	
				20			20	EA	CHANGING ELEVATION OF SEWER MANHOLE	604.42	EST
						175	175	HR	POWER GRADER RENTAL	608.15	EST
						175	175	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST
						115	115	HR	POWER BROOM RENTAL	608.30	EST
						175	175	HR	POWER BROOM RENTAL, TYPE II	608.31	EST
						175	175	HR	TRUCK RENTAL	608.37	EST
						175	175	HR	LOADER RENTAL, TYPE I	608.40	EST
						~~18,975~~ 0	~~18,975~~ 0	CM	DUST CONTROL W/WATER	609.10	
						2403.1	2403.1				
						~~1750~~	~~1750~~	CM	STONE FILL, TYPE I	613.10	
						~~100~~ 14	~~100~~ 14	CM	STONE FILL, TYPE II	613.11	EST
						~~285~~ 130	~~285~~ 130	M	TREATED TIMBER CURB	616.35	2
						~~3~~ 2	~~3~~ 2	EA	RELOCATE MAIL BOX, SINGLE SUPPORT	617.10	
						~~3~~ 2	~~3~~ 2	EA	RELOCATE MAIL BOX, MULTIPLE SUPPORT	617.12	
				2407.8	2407.8	~~2340~~	~~2340~~	M	STEEL BEAM GUARD RAIL	621.20	4
				2787.4	2787.4	~~2630~~	~~2630~~	M	STEEL BEAM GUARD RAIL (MOD. - W/2.4 M POSTS)	621.20	3
						~~53~~ 33	~~53~~ 33	EA	MANUFACTURED TERMINAL SECTION (FLARED)	621.505	
						4	4	EA	TERMINAL CONNECTOR FOR STEEL BEAM GUARD RAIL	621.53	
						~~11~~ 29	~~11~~ 29	EA	ANCHOR FOR STEEL BEAM GUARD RAIL	621.60	
						5670	5670				
						~~5505~~	~~5505~~	M	REMOVAL AND DISPOSAL OF GUARD RAIL	621.80	1
				~~11~~ 9			~~11~~ 9	EA	ADJUST ELEVATION OF VALVE BOX	629.20	EST
						~~690~~ 0	~~690~~ 0	HR	UNIFORMED TRAFFIC OFFICERS	630.10	
						1500	1500	HR	FLAGGERS	630.15	
						1	1	LS	TESTING EQUIPMENT - BITUMINOUS (MOD.)	631.17	
						1	1	LS	MOBILIZATION	635.10	
						1	1	LS	TRAFFIC CONTROL	641.10	

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		MEDIUM DUTY BITUMINOUS CONCRETE PAVEMENT
		(PG 58-34)
5563	T	LEVELING COURSE TYPE III
8053	T	WEARING COURSE TYPE IV
384	T	ROUNDING
14,000	T	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: CAMBRIDGE
PROJECT NUMBER: STP 2218(1)S

FILE NAME: _/pave/99c188/99c188.dgn
PROJECT LEADER: WOOLAVER
DESIGNED BY: LOCKE
RECORDED BY: LOCKE
PLOT DATE: 14-FEB-2006 16:4
DRAWN BY: LOCKE
CHECKED BY: PAVT MGMT
SHEET 4 OF 28