STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET 1

APPROXIMATE SUMMARY OF QUANTITIES

EMPLOYEE TRAINEESHIP	NON-GOV'T PARTICIPATING	GOV'T PARTICIPATING BRIDGE	GOV'T PARTICIPATING ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
			5	5	EA	THINNING AND TRIMMING	201.31	EST
			100	100	YD3	COMMON EXCAVATION	203.15	EST
			5,000	5,000	YD3	EARTH BORROW	203.30	EST
			1	1	YD3	TRENCH EXCAVATION OF EARTH (N.A.B.I.)	204.20	--
			3,100	3,100	YD2	COLD PLANING - BITUMINOUS PAVEMENT	210.10	77
			12,500	12,500	T	SUBBASE OF CRUSHED GRAVEL (FINE GRADED)	301.28	112
			78,500	78,500	YD2	RECLAIMED STABILIZED BASE	310.20	335
			6,000	6,000	T	AGGREGATE SHOULDERS	402.12	25
			1,050	1,050	CWT	EMULSIFIED ASPHALT	404.65	EST
			21,500	21,500	T	MEDIUM DUTY BITUMINOUS CONC. PAVE. (PG 58-34)	406.27	369
			1	1	LU	PRICE ADJ. ASPHALT CEMENT (N.A.B.I.)	406.50	--
		1		1	YD3	CONCRETE, CLASS A	501.22	--
		200		200	LB	REINFORCING STEEL	507.15	--
		50		50	LF	BRIDGE EXPANSION JOINT (ASPHALTIC PLUG)	516.10	--
		130		130	LF	REMOVAL OF EXISTING RAILING	525.10	5
		130		130	LF	BRIDGE RAILING-H.D.S.B. FASCIA MOUNTED (MOD 1)	525.41	5
		1		1	YD3	REMOVAL OF CONCRETE OR MASONRY	529.25	--
			220	220	LF	15'' CSP .064 (2-2/3 X 1/2)	601.0010	EST
			200	200	LF	18'' CSP .064 (2-2/3 X 1/2)	601.0015	EST
			80	80	LF	18'' CPEP	601.0915	--
			20	20	EA	15'' CSPES .064 (2-2/3 X 1/2)	601.6010	EST
			20	20	EA	18'' CSPES .064 (2-2/3 X 1/2)	601.6015	EST
			3	3	EA	CHANGING ELEVATION OF DI, CB OR MH, CLASS I	604.40	EST
			12	12	EA	REHABILITATION OF DI, CB OR MH, CLASS I	604.412	EST
			300	300	LF	6'' UNDERDRAIN	605.10	EST
			90	90	HR	POWER GRADER RENTAL	608.15	EST
			700	700	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST
			65	65	HR	POWER BROOM RENTAL	608.30	EST
			1,400	1,400	HR	TRUCK RENTAL	608.37	EST
			90	90	HR	LOADER RENTAL, TYPE I	608.40	EST
			10	10	T	DUST AND ICE CONTROL W/CALCIUM CHLORIDE	609.15	EST
			825	825	YD3	STONE FILL, TYPE I	613.10	16
			200	200	LF	GRANITE SLOPE EDGING	616.20	6
			200	200	LF	TREATED TIMBER CURB	616.35	EST
			25	25	T	BITUM. CONCRETE GUTTER AND TRAFFIC ISLANDS	616.47	2.73
			1	1	EA	RELOCATE MAILBOX, SINGLE SUPPORT	617.10	--
			125	125	EA	YIELDING MARKER POSTS	619.17	--
			1,225	1,225	LF	STEEL BEAM GUARD RAIL (GALVANIZED)	621.20	25
			1,500	1,500	LF	STEEL BEAM GUARD RAIL (GALV.)(MOD.-W/8' POSTS)	621.20	12.5
			225	225	LF	HEAVY DUTY STEEL BEAM GUARD RAIL (GALVANIZED)	621.21	25
			27	27	EA	MANUFACTURED TERMINAL SECTION (FLARED)	621.505	--
			1	1	EA	MANUFACTURED TERMINAL SECTION (TANGENT)	621.505	--
			25	25	EA	ANCHOR FOR STEEL BEAM RAIL	621.60	--

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		COLD PLANING - BITUMINOUS PAVEMENT
145	YD2	BEGIN PROJECT
722	YD2	MAINLINE STA 158+50 TO STA 161+00 (BR 5)
1,011	YD2	MAINLINE STA 250+00 TO STA 253+50 (BR 8)
1,000	YD2	TOWN HIGHWAYS AND DRIVES
145	YD2	END PROJECT
77	YD2	ROUNDING
3,100	YD2	TOTAL
		MEDIUM DUTY BITUMINOUS CONC. PAVEMENT (PG 58-34)
		TYPE II (BINDER)
12,763	T	MAINLINE
444	T	TOWN HIGHWAYS AND DRIVES
		TYPE III (WEARING)
7,657	T	MAINLINE
267	T	TOWN HIGHWAYS AND DRIVES
369	T	ROUNDING
21,500	T	TOTAL
		SUBBASE OF CRUSHED GRAVEL (FINE GRADED)
1,000	T	ESTIMATED QUANTITIES FOR TOWN HIGHWAYS & DRIVES
10,210	T	RECLAIMED STABILIZED BASE
1,178	T	REPLACEMENT FOR UNSUITABLE SHOULDER MATERIAL
112	T	ROUNDING
12,500	T	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

STATIONS FROM	STATIONS TO	PAVEMENT WIDTHS			EQUATIONS +	EQUATIONS -	FEET	MILES	REMARKS

TOTALS

QUANTITY SHEET #1

PROJECT NAME **MORGAN** pave/99cl92/99cl92.dgn
PROJECT NUMBER **AC STP 2220(1)S** 99cl92qsl.i

DATE PLOTTED 12-MAR-2007 11:35