STATE OF VERMONT
AGENCY OF TRANSPORTATION

COMPOSITE QUANTITY SHEET 2

VAOT Metric

			BENNINGTON NH 2225(1)S		BENNINGTON NH 2202(1)S		APPROXIMATE SUMMARY OF QUANTITIES				
				ROADWAY	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
						7	7	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-
				10600		13850	24450	m	DURABLE 100 mm WHITE LINE	646.40	1210
				10100		12300	22400	m	DURABLE 100 mm YELLOW LINE	646.41	1060
						220	220	m	DURABLE 200 mm WHITE LINE	646.42	11
						160	160	m	DURABLE 200 mm YELLOW LINE	646.43	11
				35			35	m	DURABLE 600 mm STOP BAR	646.46	1.7
						190	190	m	DURABLE 600 mm STOP BAR (TYPE 1 TAPE)	646.46	9.4
				28			28	EA	DURABLE LETTER OR SYMBOL	646.50	
						144	144	EA	DURABLE LETTER OR SYMBOL (TYPE 1 TAPE)	646.50	-
						700	700	m	DURABLE CROSSWALK MARKINGS WITH DIAGONAL LINES (MOD.)	646.51	33.3
						27200	27200	m	TEMPORARY 100 mm WHITE LINE	646.60	1300
				60		24600	24660	m	TEMPORARY 100 mm YELLOW LINE	646.61	1258
				35		380	415	m	TEMPORARY 600 mm STOP BAR	646.66	20.5
				28		228	256	EA	TEMPORARY LETTER OR SYMBOL	646.70	-
						1400	1400	m	TEMPORARY CROSSWALK MARKINGS WITH DIAGONAL LINES	646.71	66.6
				450		1750	2200	EA	LINE STRIPING TARGETS	646.76	112
				15		50	65	kg	SEED	651.15	EST.
				115		115	230	kg	FERTILIZER	651.18	EST.
				1		1	2	t	AGRICULTURAL LIMESTONE	651.20	EST.
				1		1	2	t	HAY MULCH	651.25	EST.
				25		100	125	m^3	TOPSOIL	651.35	EST.
				43		73	116	m^2	TRAFFIC SIGNS, TYPE A	675.20	1.04
				4			4	m^2	TRAFFIC SIGNS, TYPE B	675.21	0.76
				440		355	795	m	FLANGED CHANNEL SIGN POSTS-BEGIN OPTION ITEM	675.301	45.2
				440		355	795	m	SQUARE TUBE SIGN POSTS AND ANCHOR-END OPTION ITEM	675.341	45.2
						2	2	m	FLANGED CHANNEL SIGN POSTS (MOD.)	675.301	-
						515	515	kg	TUBULAR ALUMINUM SIGN POSTS (MOD.)	675.32	27.8
				30			30	kg	TUBULAR ALUMINUM SIGN POSTS	675.32	3
				120		240	360	EA	REMOVING SIGNS	675.50	-
				16		29	45	EA	ERECTING SALVAGED SIGNS	675.60	-
				1			1	EA	FLASHING BEACON-GROUND MOUNTED (MOD.)	678.16	
						1450	1450	m	VEHICLE LOOP DETECTOR	678.22	70
						46	46	m	WIRED CONDUIT (55 mm)	678.23	3
						28	28	EA	JUNCTION BOX	678.26	-

DETAILED SUMMARY OF QUANTITIES		
QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES		
QUANTITIES	UNIT	ITEMS

STATIONS		PAVEMENT WIDTHS			EQUATIONS				REMARKS
FROM	TO				+	-			
TOTALS									