STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET 1

VAOT Metric

APPROXIMATE SUMMARY OF QUANTITIES

			NON GOV'T PARTICIPATING	EMPLOYEE TRAINEESHIP	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
			-	-	-	75	75	m^3	COMMON EXCAVATION	203.15	6
			-	-	-	37	37	m^3	SOLID ROCK EXCAVATION	203.16	2.2
			-	-	-	0.5	0.5	m^3	TRENCH EXCAVATION OF EARTH (NOT A BID ITEM)	204.20	-
			-	-	-	68600	68600	m^2	COLD PLANNING - BITUMINOUS PAVEMENT	210.10	3299
			-	-	-	140	140	m^2	SCARIFYING PAVEMENT (MOD.)	212.20	8
			-	-	-	95	95	t	SUBBASE OF CRUSHED GRAVEL (FINE GRADED)	301.28	6
			-	-	-	16400	16400	kg	EMULSIFIED ASPHALT	404.65	801
			-	-	-	1	1	LU	PRICE ADJUSTMENT ASPHALT CEMENT (NOT A BID ITEM)	406.50	-
			-	-	-	8200	8200	t	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (PG 64-28)	490.30	413
			-	-	10	-	10	m	BRIDGE EXPANSION JOINT	516.10	0.4
			-	-	-	89	89	EA	CHANGE ELEVATION OF DI, CB OR MH	604.40	-
			-	-	-	12	12	EA	REHABING DI, CB OR MH, CLASS I	604.412	-
			-	-	-	85	85	EA	CHANGE ELEVATION OF SEWER MANHOLE	604.42	-
			-	-	-	80	80	HR	POWER GRADER RENTAL	608.15	-
			-	-	-	80	80	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.
			-	-	-	80	80	HR	POWER BROOM RENTAL	608.30	-
			-	-	-	160	160	HR	POWER BROOM RENTAL, TYPE II	608.31	EST.
			-	-	-	160	160	HR	TRUCK RENTAL	608.37	EST.
			-	-	-	17	17	t	DUST AND ICE CONTROL WITH CALCIUM CHLORIDE	609.15	1
			-	-	-	81	81	m	CAST IN PLACE CONCRETE CURB, TYPE B	616.28	4
			-	-	-	11	11	m	REMOVING AND RESETTING CURB	616.40	1
			-	-	-	112	112	m	REMOVAL OF EXISTING CURB	616.41	6.5
			-	-	-	25	25	t	BITUMINOUS CONCRETE GUTTERS & TRAFFIC ISLANDS	616.47	1.2
			-	-	-	200	200	m^2	PORTLAND CEMENT CONCRETE SIDEWALK, 125 mm	618.10	10.9
						420	420	m^2	BRICK PAVING (MOD.)	618.20	
			-	-	-	2	2	EA	YIELDING MARKER POSTS	619.17	-
			-	-	-	71	71	EA	ADJUST ELEVATION OF VALVE BOX	629.20	-
			-	-	-	3800	3800	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.
			-	-	-	5700	5700	HR	FLAGGERS	630.15	EST.
			-	-	-	1	1	LS	FIELD OFFICE - ENGINEERS	631.10	-
			-	-	-	1	1	LS	TESTING EQUIPMENT - CONCRETE	631.16	-
			-	-	-	1	1	LS	TESTING EQUIPMENT - BITUMINOUS	631.17	-
			-	-	-	1	1	LS	FIELD OFFICE - TELEPHONE (NOT A BID ITEM)	631.25	-
			-	-	-	1	1	LS	MOBILIZATION	635.10	-
			-	-	-	1	1	LS	TRAFFIC CONTROL	641.10	-
			-	-	-	1	1	LS	TRAFFIC CONTROL (MOD. 1)	641.10	-
			-	-	-	1	1	LS	TRAFFIC CONTROL (MOD. 2)	641.10	-

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		COLD PLANING - BITUMINOUS PAVEMENT
48488	m^2	VT. ROUTE 9
8037	m^2	U.S. ROUTE 7
8168	m^2	SIDE ROADS
608	m^2	DRIVEWAYS & PARKING AREAS
3299	m^2	ROUNDING
68600	m^2	TOTAL
		SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (PG 64-28)
4719	t	WEARING COURSE (TYPE IVS)
2032	t	LEVELING COURSE (TYPE IVS)
981	t	SIDE ROADS
55	t	DRIVEWAYS
413	t	ROUNDING
8200	t	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

STATIONS		PAVEMENT WIDTHS			EQUATIONS				REMARKS
FROM	TO				+	-			
TOTALS									

/pave/99d156/pd156.dgn pd156qs1.1

PROJECT NAME BENNINGTON
PROJECT NUMBER NH 2202(I)S

FILE NAME =$FILE$
DATE/TIME =$DATE$