ITEM DETAIL SUMMARY SHEET 3

VDOT Metric

LOCATION			GUARDRAIL						MISCELLANEOUS										REMARKS
			621.20	621.20	621.52	621.60	621.80	621.81	203.15	203.16	203.28	212.20	301.28	616.28	616.40	616.41	618.10	619.17	
STATION	STATION	POS.	STEEL BEAM G.R.	2.4 m STEEL BEAM G.R. (MOD.)	MANUF. TERM. SECTION	ANCHOR FOR G.R	REMOVE & DISP. G.P.	REMOVE & DISP. G.R.	COMMON EXCAVATION	SOLID ROCK EXCAVATION	EXCAVATION OF SURFACES & PAVEMENTS	SCARIFYING PAVEMENT (MOD.)	SUBBASE OF CRUSHED GRAVEL	CAST IN PLACE PCC CURB TYPE B	REMOVE & RESET CURB	REMOVAL OF EXIST. CURB	P.C.C. SIDEWALK 125 mm	YEILD. MKR. POST	
			m	m	EA	EA	EA	m	m^3	m^3	m^3	m^2	t	m	m	m	m^2	EA	
U.S. ROUTE 7																			
4+752.0		LT													2.5				
4+795.0		RT													2.5				
5+178.0		LT							5	2.5			4	6		7.5	11.5		CONSTRUCT SIDEWALK RAMP, TYPE 6.
5+286.0		RT										5							SEE SHEET 70 OF 108 FOR SIDEWALK RAMP TEXTURING DETAIL.
5+294.0		RT										5							SEE SHEET 70 OF 108 FOR SIDEWALK RAMP TEXTURING DETAIL.
5+440.0		LT							0.9	0.5			1.1	1.8		1.8	3.2		CONSTRUCT SIDEWALK PANEL.
5+456.0		RT										5							SEE SHEET 70 OF 108 FOR SIDEWALK RAMP TEXTURING DETAIL.
5+462.0		LT							0.9	0.5			1.1	1.8		1.8	3.2		CONSTRUCT SIDEWALK PANEL.
LENGTH OF PROJECT		LT. & RT.											12.4						NEW DRIVEWAY SUBBASE MATERIAL
SHEET SUBTOTAL									6.8	3.5		15	6.2	9.6	5.0	11.1	17.9	-	
SHEET 7 SUBTOTAL									31.2	15.6		54	30.7	35.5	5.0	53.5	82.9	2	
SHEET 8 SUBTOTAL									31	15.7		63	31.7	31.9	-	40.9	88.3	-	
ROUNDING									6	2.2		8	6.4	4	1	6.5	10.9	-	
TOTAL									75	37		140	95	81	11	112	200	2	

DATUM
VERTICAL N/A
HORIZONTAL N/A

FILE NAME =$FILE$
DATE/TIME =$DATE$
USER =$NTUSER$

ITEM DETAIL SUMMARY SHEET #3

SURVEYED BY N/A DATE N/A
DRAWN BY J.A.R. DATE 4/01
SQUAD LEADER T.P.K.
DESIGN FILE NO. pave/99d156/pd156.dgn
IPARM FILE pd156id3.1 DATE PLOTTED 21-NOV-2005
PROJ. NAME BENNINGTON
PROJ. NO. NH 2202(1)S
SHEET 13 OF 108 SHEETS