STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 3

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	FOUNDATION	TUBULAR STEEL Ø (mm) kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																									
BENNINGTON: VT. ROUTE 9 5+533.0, LT	ONE WAY ONE WAY	1 1	900 900	300 300	0.27 0.27						1			3.66 X			X																BACK - TO - BACK		E-142M E-142M
5+539.0, LT	ONE WAY ONE WAY	1 1	900 900	300 300	0.27 0.27						1			3.66 X			X																BACK - TO - BACK		E-142M E-142M
5+564.0, LT	STOP 0090 0202 0346	1 1	750 150	750 200	0.56 0.03						1			4.27 X			X																BACK - TO - BACK		E-143M E-138M
5+565.0, RT	ONE WAY ONE WAY	1 1	900 900	300 300	0.27 0.27						1			3.66 X			X																BACK - TO - BACK		E-142M E-142M
5+576.0, RT	ONE WAY ONE WAY	1 1	900 900	300 300	0.27 0.27						1			3.66 X			X																BACK - TO - BACK		E-142M E-142M
												m	m	m 23.0	m	m	m 23.0	EA	kg	kg	kg		kg	kg	kg	kg									
TOTALS			m² 2.75	m²	EA	m²						m 23.0			m 23.0					kg		EA		kg			EA	EA	kg						

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT:	PROJECT NO.:
BENNINGTON	NH 2202(I)S

DESIGN FILE NAME: pave/99dl56/pdl56.dgn
IPARM FILE NAME: pdl56ss03.i
SURVEYED BY: N/A
SQUAD LEADER: T.P.K.
PLOT DATE: 2I-NOV-2005 I0:
SURVEY DATE: N/A
DRAWN BY: C.A.K.
SHEET: 50 OF I08