STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 6

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	FOUNDATION	TUBULAR STEEL Ø (mm) kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
														OPTION ITEMS																							
BENNINGTON: VT. ROUTE 9 6+330.0, RT	MAIN ST McCALL ST	1	600	150	0.09		1				1			4.27 X			X																	SALVAGED SIGN TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGN ON FLANGED CHANNEL POST.	-	E-123M -
	STOP 0090 0202 0393	1 1	750 150	750 200	0.56 0.03																													BACK - TO - BACK		E-143M E-138M
6+368.0, LT	MAIN ST McKINLEY ST						1 1				1			4.27 X			X																	SALVAGED SIGNS TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGNS ON FLANGED CHANNEL POST.	-	-
	STOP 0090 0202 0396	1 1	750 150	750 200	0.56 0.03																													BACK - TO - BACK		E-143M E-138M
6+505.0, LT	SPEED LIMIT 30	1	600	750	0.45						1			4.27 X			X																			E-142M
6+528.0, RT	MAIN ST HARRISON AVE	1	600	150	0.09		1				1			4.27 X			X																	SALVAGED SIGN TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGN ON FLANGED CHANNEL POST.	-	E-123M -
	STOP 0090 0202 0405	1 1	750 150	750 200	0.56 0.03																													BACK - TO - BACK		E-143M E-138M
6+585.0, LT	WEST	1	600	300	0.18						1									8.8														USE 70 mm DIAMETER TUBULAR ALUMINUM SIGN POST PAINTED BLACK. PAYMENT UNDER ITEM 675.32 TUBULAR ALUMINUM SIGN POST (MOD.).		E-136BM
	VERMONT 9	1	600	600	0.36																															E-136BM
6+597.0, RT	STOP HERE ON RED	1	600	900	0.54						1									8.8														USE 70 mm DIAMETER TUBULAR ALUMINUM SIGN POST PAINTED BLACK. PAYMENT UNDER ITEM 675.32 TUBULAR ALUMINUM SIGN POST (MOD.).		E-140M
											m	m	m 18.4		m	m	m 18.4	EA	kg	kg	kg		kg	kg	kg	kg								
TOTALS			m² 3.48		m²	EA 4	m²				m 18.4				m 18.4				kg 17.6			EA	kg				EA	EA	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT:	PROJECT NO.:
BENNINGTON	NH 2202(I)S

DESIGN FILE NAME: pave/99dl56/pdl56.dgn
IPARM FILE NAME: pdl56ss06.i
SURVEYED BY: N/A
SQUAD LEADER: T.P.K.
PLOT DATE: 21-NOV-2005 10:
SURVEY DATE: N/A
DRAWN BY: C.A.K.
SHEET: 53 OF 108