STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 10

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	FOUND-ATION	TUBULAR STEEL Ø (mm) kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																							
BENNINGTON VT. ROUTE 9: 7+134.0, LT	RESERVED PARKING	1	300	450	0.14						1									~~8.8~~	GIVE SIGN TO TOWN												USE 70 mm DIAMETER TUBULAR ALUMINUM SIGN POST PAINTED BLACK. PAYMENT UNDER ITEM 675.32 TUBULAR ALUMINUM SIGN POST (MOD.).	69	-
7+155.0, LT	ONLY	1	900	750	0.68						1									8.4 8.8													USE 70 mm DIAMETER TUBULAR ALUMINUM SIGN POST PAINTED BLACK. PAYMENT UNDER ITEM 675.32 TUBULAR ALUMINUM SIGN POST (MOD.).		E-145AM
~~7+188.0~~, RT 7+213	RESERVED PARKING	1	300	450	0.14						1									7.8 8.8	REMOVE & RESET SIGN @ 7+213												USE 70 mm DIAMETER TUBULAR ALUMINUM SIGN POST PAINTED BLACK. PAYMENT UNDER ITEM 675.32 TUBULAR ALUMINUM SIGN POST (MOD.).	69	-
7+230.0, LT	WEST	1	450	225	0.10						1									10.4 11.8												X	USE 70 mm DIAMETER TUBULAR ALUMINUM SIGN POST PAINTED BLACK. PAYMENT UNDER ITEM 675.32 TUBULAR ALUMINUM SIGN POST (MOD.).REDUCE MINIMUM STANDARD SIZE SIGN DIMENSIONS BY 25%.		E-136BM
	VERMONT 9	1	450	450	0.20																												REDUCE MINIMUM STANDARD SIZE SIGN DIMENSIONS BY 25%.		E-136BM
	↑	1	395	280	0.11																												REDUCE MINIMUM STANDARD SIZE SIGN DIMENSIONS BY 25%.		E-136BM
	SOUTH NORTH	1 1	450 450	225 225	0.10 0.10																												REDUCE MINIMUM STANDARD SIZE SIGN DIMENSIONS BY 25%.		E-136AM E-136AM
	7 7	1 1	450 450	450 450	0.20 0.20																												REDUCE MINIMUM STANDARD SIZE SIGN DIMENSIONS BY 25%.		E-136AM E-136AM
	← →	1 1	395 395	280 280	0.11 0.11																												REDUCE MINIMUM STANDARD SIZE SIGN DIMENSIONS BY 25%.		E-136AM E-136AM
												m	m	m	m	m	m		EA	kg 38.2	kg	kg		kg	kg	kg	kg								
TOTALS					m² 2.19	m²	EA	m²				m			m					kg 38.2			EA	kg				EA	EA	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT: BENNINGTON	PROJECT NO.: NH 2202(1)S
DESIGN FILE NAME: pave/99d156/pd156.dgn	
IPARM FILE NAME: pd156ss10.I	PLOT DATE: 21-NOV-2005 10:
SURVEYED BY: N/A	SURVEY DATE: N/A
SQUAD LEADER: T.P.K.	DRAWN BY: C.A.K.
	SHEET: 57 OF 108