STATE OF VERMONT
AGENCY OF TRANSPORTATION

DETOUR SIGN SUMMARY SHEET 3

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	FOUNDATION	TUBULAR STEEL Ø (mm) kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																									
8	DETOUR	1	600	300	0.18						1									8.8															72	-
	SOUTH	1	600	300	0.18																															E-136AM
	7	1	600	600	0.36																															E-136AM
		1	525	375	0.20																															E-136AM
9	END	2	600	300	0.36						2									17.6															TWO DIFFERENT LOCATIONS, ONE POST PER EACH LOCATION.		E-140M
	DETOUR	2	600	300	0.36																														72	-
	NORTH OR SOUTH	2	600	300	0.36																															E-136AM
	7	2	600	600	0.72																															E-136AM
10	DETOUR	1	450	225	0.10						1									12.5														X	REDUCE MINIMUM STANDARD SIZE SIGN DIMENSIONS BY 25%.	72	-
	EAST	1	450	225	0.10																														REDUCE MINIMUM STANDARD SIZE SIGN DIMENSIONS BY 25%.		E-136BM
	VERMONT 9	1	450	450	0.20																														REDUCE MINIMUM STANDARD SIZE SIGN DIMENSIONS BY 25%.		E-136BM
		1	395	280	0.11																														REDUCE MINIMUM STANDARD SIZE SIGN DIMENSIONS BY 25%.		E-136BM
	NORTH SOUTH	1 1	450 450	225 225	0.10 0.10																														REDUCE MINIMUM STANDARD SIZE SIGN DIMENSIONS BY 25%.		E-136AM E-136AM
	7 7	1 1	450 450	450 450	0.20 0.20																														REDUCE MINIMUM STANDARD SIZE SIGN DIMENSIONS BY 25%.		E-136AM E-136AM
		1 1	395 395	280 280	0.11 0.11																														REDUCE MINIMUM STANDARD SIZE SIGN DIMENSIONS BY 25%.		E-136AM E-136AM
TOTALS					m² 4.05	m²	EA	m²				m	m	m	m	m	m		EA	kg 38.9	kg	kg	EA	kg	kg	kg	kg	EA	EA	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT:	PROJECT NO.:
BENNINGTON	NH 2202(I)S

DESIGN FILE NAME: /pave/99dl56/pdl56.dgn
IPARM FILE NAME: pdl56dss3.i
SURVEYED BY: N/A
SQUAD LEADER: T.P.K.
PLOT DATE: 21-NOV-2005 10:
SURVEY DATE: N/A
DRAWN BY: C.A.K.
SHEET: 75 OF 108