STATE OF VERMONT
AGENCY OF TRANSPORTATION

DETOUR SIGN SUMMARY SHEET 5

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) 44 kg/m 3.4	50 kg/m 3.9	63 kg/m 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) 75 kg/m 1.9	100 kg/m 2.5	100 MOD kg/m 2.5	TUBULAR STEEL Ø (mm) FOUND-ATION	75 kg/m 11.3	89 kg/m 13.4	100 kg/m 16.1	125 kg/m 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																									
13	DETOUR	1	450	225	0.10						1									12.5													X	REDUCE MINIMUM STANDARD SIZE SIGN DIMENSIONS BY 25%.	72	-
	SOUTH	1	450	225	0.10																													REDUCE MINIMUM STANDARD SIZE SIGN DIMENSIONS BY 25%.		E-136AM
	7	1	450	450	0.20																													REDUCE MINIMUM STANDARD SIZE SIGN DIMENSIONS BY 25%.		E-136AM
	→	1	395	375	0.11																													REDUCE MINIMUM STANDARD SIZE SIGN DIMENSIONS BY 25%.		E-136AM
	EAST WEST	1 1	450 450	225 225	0.10 0.10																													REDUCE MINIMUM STANDARD SIZE SIGN DIMENSIONS BY 25%.		E-136BM E-136BM
	VERMONT 9 VERMONT 9	1 1	450 450	450 450	0.20 0.20																													REDUCE MINIMUM STANDARD SIZE SIGN DIMENSIONS BY 25%.		E-136BM E-136BM
	← →	1 1	395 395	375 375	0.11 0.11																													REDUCE MINIMUM STANDARD SIZE SIGN DIMENSIONS BY 25%.		E-136BM E-136BM
14	DETOUR	1	450	225	0.10						1									12.5													X	REDUCE MINIMUM STANDARD SIZE SIGN DIMENSIONS BY 25%.	72	-
	EAST	1	450	225	0.10																													REDUCE MINIMUM STANDARD SIZE SIGN DIMENSIONS BY 25%.		E-136BM
	VERMONT 9	1	450	450	0.20																													REDUCE MINIMUM STANDARD SIZE SIGN DIMENSIONS BY 25%.		E-136BM
	↰	1	395	280	0.11																													REDUCE MINIMUM STANDARD SIZE SIGN DIMENSIONS BY 25%.		E-136BM
	NORTH SOUTH	1 1	450 450	225 225	0.10 0.10																													REDUCE MINIMUM STANDARD SIZE SIGN DIMENSIONS BY 25%.		E-136AM E-136AM
	7 7	1 1	450 450	450 450	0.20 0.20																													REDUCE MINIMUM STANDARD SIZE SIGN DIMENSIONS BY 25%.		E-136AM E-136AM
	↰ ↱	1 1	395 395	280 280	0.11 0.11																													REDUCE MINIMUM STANDARD SIZE SIGN DIMENSIONS BY 25%.		E-136AM E-136AM
TOTALS					m² 2.66	m²	EA	m²				m	m	m	m	m	m		EA	kg 25.0	kg	kg	EA	kg	kg	kg	kg	EA	EA	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT:	PROJECT NO.:
BENNINGTON	NH 2202(I)S

DESIGN FILE NAME: /pave/99dl56/pdl56.dgn
IPARM FILE NAME: pdl56dss5.i
SURVEYED BY: N/A
SQUAD LEADER: T.P.K.
PLOT DATE: 2I-NOV-2005 10:
SURVEY DATE: N/A
DRAWN BY: C.A.K.
SHEET: 77 OF 108