STATE OF VERMONT
AGENCY OF TRANSPORTATION

DETOUR SIGN SUMMARY SHEET 6

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	FOUNDATION	TUBULAR STEEL Ø (mm) kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																									
15	DETOUR	2	450	225	0.20						2									21.2														TWO DIFFERENT LOCATIONS, ONE POST PER EACH LOCATION. REDUCE MINIMUM STANDARD SIZE SIGN DIMENSIONS BY 25%.	72	-
	EAST OR WEST	2	450	225	0.20																												REDUCE MINIMUM STANDARD SIZE SIGN DIMENSIONS BY 25%.		E-136BM
	VERMONT 9	2	450	450	0.40																												REDUCE MINIMUM STANDARD SIZE SIGN DIMENSIONS BY 25%.		E-136BM
	NORTH OR SOUTH	2	450	225	0.20																												REDUCE MINIMUM STANDARD SIZE SIGN DIMENSIONS BY 25%.		E-136AM
	7	2	450	450	0.40																												REDUCE MINIMUM STANDARD SIZE SIGN DIMENSIONS BY 25%.		E-136AM
16	DETOUR	3	600	300	0.54						3										45.0													THREE DIFFERENT LOCATIONS, ONE POST PER EACH LOCATION.	72	-
	WEST	3	600	300	0.54																														E-136BM
	VERMONT 9	3	600	600	1.08																														E-136BM
	TO	3	600	300	0.36																														E-136AM
	7	3	600	600	1.08																														E-136AM
17	DETOUR	2	600	300	0.36						2										30.0													THREE DIFFERENT LOCATIONS, ONE POST PER EACH LOCATION.	72	-
	WEST	2	600	300	0.36																														E-136BM
	VERMONT 9	2	600	600	0.72																														E-136BM
	TO	2	600	300	0.36																														E-136AM
	7	2	600	600	0.72																														E-136AM
	OR	2	525	375	0.40																														E-136AM
												m	m	m	m	m	m		EA	kg 21.2	kg 75	kg		kg	kg	kg	kg								
	TOTALS				m² 7.92	m²	EA	m²				m			m					kg 96.2			EA	kg				EA	EA	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT:	PROJECT NO.:
BENNINGTON	NH 2202(I)S

DESIGN FILE NAME: /pave/99dl56/pdl56.dgn
IPARM FILE NAME: pdl56dss6.i
SURVEYED BY: N/A
SQUAD LEADER: T.P.K.
PLOT DATE: 21-NOV-2005 10:
SURVEY DATE: N/A
DRAWN BY: C.A.K.
SHEET: 78 OF 108