STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET 1

VAOT Metric

APPROXIMATE SUMMARY OF QUANTITIES

			NON GOV'T PARTICIPATING	EMPLOYEE TRAINEESHIP	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
			-	-	-	10	10	m^3	COMMON EXCAVATION	203.15	EST.
			-	-	-	300	300	m^3	EARTH BORROW	203.30	20
			-	-	-	0.5	0.5	m^3	TRENCH EXCAVATION OF EARTH (NOT A BID ITEM)	204.20	-
			-	-	-	2200	2200	m^2	COLD PLANING - BITUMINOUS PAVEMENT	210.10	84
			-	-	-	350	350	t	SUBBASE OF CRUSHED GRAVEL (FINE GRADED)	301.28	35
			-	-	-	450	450	t	AGGREGATE SHOULDERS	402.12	30
			-	-	-	8400	8400	kg	EMULSIFIED ASPHALT	404.65	388
			-	-	-	3900	3900	t	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (PG 64-28)	490.30	217
			-	-	-	1	1	EA	CHANGE ELEVATION OF DI, CB OR MH	604.40	-
			-	-	-	11	11	EA	REHABING DI, CB OR MH, CLASS I	604.412	-
			-	-	-	40	40	HR	POWER GRADER RENTAL	608.15	-
			-	-	-	30	30	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.
			-	-	-	25	25	HR	POWER BROOM RENTAL	608.30	EST.
			-	-	-	50	50	HR	POWER BROOM RENTAL, TYPE II	608.31	EST.
			-	-	-	60	60	HR	TRUCK RENTAL	608.37	EST.
			-	-	-	100	100	m^3	STONE FILL, TYPE I	613.10	EST.
			-	-	-	3	3	t	BITUMINOUS CONCRETE GUTTERS & TRAFFIC ISLANDS	616.47	1.2
			-	-	-	40	40	EA	YIELDING MARKER POSTS	619.17	-
			-	-	-	500	500	m	STEEL BEAM GUARDRAIL W/2.4 m POSTS (MOD.)	621.20	21.2
			-	-	-	14	14	EA	MANUFACTURED TERMINAL SECTION (FLARED)	621.505	-
			-	-	-	560	560	m	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	24
			-	-	-	320	320	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.
			-	-	-	480	480	HR	FLAGGERS	630.15	EST.
			-	-	-	1	1	LS	MOBILIZATION	635.10	-

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		COLD PLANING - BITUMINOUS PAVEMENT
510	m^2	VT. ROUTE 9
1142	m^2	SIDE ROADS
464	m^2	DRIVEWAYS, PARKING AREAS & PRIVATE ROADS
84	m^2	ROUNDING
2200	m^2	TOTAL
		SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (PG 64-28)
466	t	LEVELING COURSE (TYPE IV)
3107	t	WEARING COURSE (TYPE IV)
69	t	SIDE ROADS
41	t	DRIVEWAYS, PARKING AREAS & PRIVATE ROADS
217	t	ROUNDING
3900	t	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

STATIONS		PAVEMENT WIDTHS			EQUATIONS				REMARKS
FROM	TO				+	-			
TOTALS									

/pave/00b054/pb054.dgn

pb054qsl.i

PROJECT NAME BENNINGTON
PROJECT NUMBER NH 2225(I)S