ITEM DETAIL SUMMARY SHEET

VAOT Metric

LOCATION			GUARDRAIL											REMARKS
			621.20	621.20	621.21	621.21	621.505	621.505	621.60	621.76	621.76	621.77	621.80	621.81	
STATION	STATION	POS.	STEEL BEAM G.R.	STEEL BEAM G.R. W/2.4 m POSTS (MOD.)	HEAVY DUTY STEEL BEAM G.R.	H.D. STEEL BEAM G.R. W/2.4 m POSTS (MOD.)	MANUFACTURED TERMINAL SECTION	MANUFACTURED TERMINAL SECTION (FLARED)	ANCHOR FOR G.R.	REPLACE G.R. POST ASSEMBLY	REPLACE G.R. POST ASSEMBLY W/2.4 m POSTS (MOD.)	REPLACE G.R. BEAM UNIT	REMOVE & DISP. G.R.	REMOVE & DISP. G.P.	
			m	m	m	m	EA	EA	EA	EA	EA	EA	m	EA	
BENNINGTON:															
0+164.9	0+180.1	RT		15.2				2					37		INSTALL NEW MANUFACTURED TERMINAL SECTION (FLARED) AT STA. 0+164.9 & STA. 0+180.1.
0+178.4	0+258.2	LT		79.8				2					85		INSTALL NEW MANUFACTURED TERMINAL SECTION (FLARED) AT STA. 0+178.4 & STA. 0+258.2.
0+209.1	0+345.9	RT		136.8				2					159		INSTALL NEW MANUFACTURED TERMINAL SECTION (FLARED) AT STA. 0+209.1 & STA. 0+345.9.
0+868.8	0+925.8	RT		57				2					54		INSTALL NEW MANUFACTURED TERMINAL SECTION (FLARED) AT STA. 0+868.8 & STA. 0+925.8.
0+878.6	0+935.6	LT		57				2					50		INSTALL NEW MANUFACTURED TERMINAL SECTION (FLARED) AT STA. 0+878.6 & STA. 0+935.6.
1+109.6	1+212.2	RT		102.6				2					100		INSTALL NEW MANUFACTURED TERMINAL SECTION (FLARED) AT STA. 1+109.6 & STA. 1+212.2.
1+124.8	1+155.2	LT		30.4				2					51		INSTALL NEW MANUFACTURED TERMINAL SECTION (FLARED) AT STA. 1+124.8 & STA. 1+155.2.
SHEET SUBTOTAL				478.8				14					536		
ROUNDING				21.2				-					24		
TOTAL				500				14					560		

DATUM
VERTICAL N/A
HORIZONTAL N/A

ITEM DETAIL SUMMARY SHEET

SURVEYED BY N/A DATE N/A
DRAWN BY C.A.K. DATE 12/00
SQUAD LEADER T.P.K.
DESIGN FILE NO. /pave/99dl56/pdl56.dgn
IPARM FILE pb0541d.i DATE PLOTTED $DATE$
PROJ. NAME BENNINGTON
PROJ. NO. NH 2225(I)S
SHEET 86 OF 108 SHEETS