STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET

Metric

APPROXIMATE SUMMARY OF QUANTITIES

R.O.W.	EMPLOYEE TRAINEESHIP	NON-GOV'T PARTICIPATING	GOV'T PARTICIPATING BRIDGE	GOV'T PARTICIPATING ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
				160	160	m^3	COMMON EXCAVATION	203.15	--
				5	5	m^3	EARTH BORROW	203.30	EST
				1	1	m^3	TRENCH EXCAVATION OF EARTH (N.A.B.I.)	204.20	--
				400	400	m^2	COLD PLANING - BITUMINOUS PAVEMENT	210.10	25
				460	460	T	SUBBASE OF CRUSHED GRAVEL (FINE GRADED)	301.28	EST
				180	180	T	AGGREGATE SHOULDERS	402.12	EST
				1,500	1,500	KG	EMULSIFIED ASPHALT	404.65	EST
				800	800	T	MEDIUM DUTY BITUM. CONCRETE PAVE.(PG 58-34)	406.27	7
				30	30	M	450 mm CPEP	601.0915	EST
				8	8	HR	POWER GRADER RENTAL	608.15	EST
				50	50	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST
				5	5	HR	POWER BROOM RENTAL	608.30	EST
				100	100	HR	TRUCK RENTAL	608.37	EST
				9	9	HR	LOADER RENTAL, TYPE I	608.40	EST
				300	300	m^3	STONE FILL, TYPE II	613.11	EST
				2	2	EA	YIELDING MARKER POSTS	619.17	EST
				240	240	M	STEEL BEAM GUARD RAIL	621.20	1
				70	70	M	STEEL BEAM GUARD RAIL W/2.4M POSTS (MOD)	621.20	--
				2	2	EA	MANUFACTURED TERMINAL SECTION (FLARED)	621.505	--
				60	60	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST
				100	100	HR	FLAGGERS	630.15	EST
				0.9	0.9	LS	TESTING EQUIPMENT - BITUMINOUS	631.17	--
				0.1	0.1	LS	MOBILIZATION	635.10	EST
				1,900	1,900	M	DURABLE 100 MM WHITE LINE	646.40	--
				1,900	1,900	M	DURABLE 100 MM YELLOW LINE	646.41	--
				15	15	M	DURABLE 600 MM STOP BAR	646.46	--
				22	22	EA	DURABLE LETTER OR SYMBOL	646.50	--
				100	100	EA	LINE STRIPING TARGETS	646.76	EST
				300	300	m^2	GEOTEXTILE UNDER STONE FILL	649.31	EST
				30	30	KG	SEED	651.15	EST
				300	300	KG	FERTILIZER	651.18	EST
				2	2	T	AGRICULTURAL LIMESTONE	651.20	EST
				2	2	T	HAY MULCH	651.25	EST
				10	10	m^3	TOPSOIL	651.35	EST
				0.1	0.1	LS	EROSION & SEDIMENT CONTROL PLAN	652.10	--
				20	20	HR	MONITORING EROSION & SEDIMENT CONTROL PLAN	652.20	--
				0.1	0.1	LU	FIELD MAINTENANCE OF EROSION & SEDIMENT CONTROL PLAN (N.A.B.I.)	652.30	--
				100	100	m^2	EROSION MATTING	654.10	EST
				25.0	25.0	m^2	TRAFFIC SIGNS, TYPE A	675.20	0.73
							BEGIN OPTION ITEMS		
				170	170	M	FLANGED CHANNEL SIGN POSTS	675.301	9.7
				170	170	M	SQUARE STEEL SIGN POSTS AND ANCHOR	675.341	9.7
							END OPTION ITEMS		
				9	9	EA	REMOVING SIGNS	675.50	--

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		COLD PLANING - BITUMINOUS PAVEMENT
375	m^2	BEGIN PROJECT
25	m^2	ROUNDING
400	m^2	TOTAL
		MEDIUM DUTY BITUM. CONCRETE PAVEMENT (PG 58-34)
		TYPE I
50	T	SUBBASE REPAIR
		TYPE IV
370	T	LEVELING
370	T	WEARING
3	T	DRIVES
7	T	ROUNDING
800	T	TOTAL
		SUBBASE OF CRUSHED GRAVEL
10	T	ESTIMATED QUANTITY FOR DRIVES
150	T	SHOULDERS
300	T	SUBBASE REPAIR
460	T	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

STATIONS FROM	STATIONS TO	PAVEMENT WIDTHS			EQUATIONS +	EQUATIONS -	meters	kilometers	REMARKS

TOTALS /pave/00c050/pc050.dgn pc050qsl.i

QUANTITY SHEET

PROJECT NAME **MAIDSTONE**
PROJECT NUMBER **STP 2134(1)S**

DATE PLOTTED 18-AUG-2003
SHEET **7** OF **65** SHEETS