

# ITEM DETAIL SUMMARY SHEET



LOCATION			MISCELLANEOUS ITEMS									DRAINAGE ITEMS							GUARD RAIL ITEMS										REMARKS				
STA	STA	POS.	203.15 COM. EXCAV.	203.28 EXCAV. OF SURFACES AND PAVE.	203.30 EARTH BORROW	204.20 TRENCH EXCAV. OF EARTH	204.21 TRENCH EXCAV. OF ROCK	301.28 SUBBASE OF CRUSHED GRAVEL	402.12 AGG. SHOULD.	616.30 BITUM. CONC. CURB TYPE A	616.47 B. CONC. GUTTER & TRAF. ISLAND	618.10 PORT. CEMENT CONC. WALK (125mm)	501.25 CONC. CLASS B	507.15 REIN. STEEL	604.40 CHANGE ELEV.	604.412 REHAB. D.I. CLASS I	604.47 CAST IRON GRATE TYPE D	NEW PIPE		613.11 STONE FILL TYPE II	619.17 YIELD. MARKER POSTS	621.20 STEEL POST G.R.	(MOD.)	621.505 MAN. TERMINAL SECTION	621.54 MELT	621.60 ANCHOR FOR G.R.	621.75 REMOVE AND RESET G.R.	621.76 REPLACE POST ASSEM.		621.77 REPLACE BEAM UNIT	621.80 REMOVE & DISP. OF G.R.	621.81 REMOVE & DISP. OF GUIDE POSTS	
			m 3	m 3	m 3	m 3	m 3	T	T	T	T	m 2	m 3	KG	EA	EA	EA	mm	M	m 3	EA	M	M	EA	EA	EA	M	EA	EA	M	EA		
MAIDSTONE																																	
0+000	0+930	LT&RT			5	1		160	160											450	30	200	2										ESTIMATED QUANTITIES TO BE USED AS DIRECTED BY THE RESIDENT ENGINEER.
0+297	0+628	LT									10																						INSTALL NEW STEEL BEAM GUARD RAIL.
0+417	0+461	LT	160					300	10																								REPAIR EXISTING SUBBASE.
0+635		LT																		100													
<b>SUB-TOTALS</b>			160		5	1		460	180											30	300	2	239	70	2								
<b>ROUNDING</b>			--		--	--		--	--											--	--	--	1	--	--								
<b>PROJECT TOTALS</b>			160		5	1		460	180											30	300	2	240	70	2								

## ITEM DETAIL SHEET

DESIGNED BY BCE/PJM DATE 2-02

DRAWN BY C.E.A., INC. DATE 2-02

DESIGN FILE NO. /pave/00c050/pc050.dgn

PRF FILE pc050ids DATE PLOTTED 18-AUG-2003

PROJ. NAME MAIDSTONE

PROJ. NO. STP 2134(1)S

SHEET **8** OF **65** SHEETS