STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	FOUNDATION	TUBULAR STEEL Ø (mm) kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
														OPTION ITEMS																							
MAIDSTONE 0+005 LT	STOP	1	750	750	0.56						1			X		X																					E-143M
0+026 RT	STOP	1	750	750	0.56						2			X		X																		MOUNT STOP SIGN BACK TO BACK WITH THE POSTED BRIDGE SIGN.		E-143M
	POSTED BRIDGE 3000 FEET AHEAD WEIGHT LIMIT 20T	1	1650	1050	1.73																														18	
0+070 LT	SOUTH NORTH	1	600 600	300 300	0.18 0.18						2			X		X																					E-136BM E-136BM
	VERMONT 102 VERMONT 102	1	750 750	600 600	0.45 0.45																															E-136BM E-136BM
	← →	1	525 525	375 375	0.20 0.20																															E-136BM E-136BM
0+086 RT	STRATFORD N.H. 1	1	1800	250	0.45						2			X		X																					E-123M
0+130 LT	← GUILDHALL 7	1	1800	250	0.45						2			X		X																					E-123M
	BLOOMFIELD 9 →	1	1800	250	0.45																															E-123M
0+146 RT	SPEED LIMIT 50	1	600	750	0.45						1			X		X																					E-142M
				m 2	m 2	EA.	m 2				m	m	m	m	m	m		EA.	kg	kg	kg	EA.	kg	kg	kg	kg	EA.	EA.	kg						
													39.7			39.7																			
			SHEET TOTALS	6.31							39.7				39.7																					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT: **MAIDSTONE**	PROJECT NO.: **STP 2134(1)S** DATE: 2-02
DESIGN FILE NAME: **/pave/00c050/pc050.dgn** IPARM FILE NAME: **pc050ts3** SURVEYED BY: SQUAD LEADER:	PLOT DATE: 18-AUG-2003 SURVEY DATE: DRAWN BY: LFW SHEET: **14** OF **65**