

QUANTITY SHEET #2

SUMMARY OF ESTIMATED QUANTITIES													TOTALS			DESCRIPTIONS			DETAILED SUMMARY OF QUANTITIES							
													E&C	STP EH01(21)	LANDSCAPING	EROSION CONTROL	PARK-AND- RIDE	ROUND	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	QUANTITIES	UNIT	ITEMS
																	19	0	19		EA	BOUNDARY MARKERS	619.10			
																3395		25	3420		SY	SNOW FENCE (MOD. - PDF)	620.70			
																973		12	985		SY	SNOW FENCE (MOD. - ARCH)	620.70			
														1				0	1		MFBM	INSULATION BOARD	622.10			
														20				0	20		LF	SEAMLESS COPPER WATER TUBE (3/4")	629.23			
														3				0	3		EACH	GATE VALVE WITH VALVE BOX (8") (MOD.)	629.27			
														1				0	1		EACH	GATE VALVE WITH VALVE BOX (8") (MOD.)	629.27			
														1				0	1		EACH	HYDRANT (MOD.)	629.28			
														450				0	450		LF	PLASTIC WATER PIPE, RIGID (6")	629.33			
														595				0	595		LF	PLASTIC WATER PIPE, RIGID (8")	629.33			
														790				10	800		LB	DUCTILE IRON FITTINGS (MOD.)	629.38			
																	40	EST.	40		HR	UNIFORMED TRAFFIC OFFICERS	630.10			
																	80	EST.	80		HR	FLAGGERS	630.15			
														1				0	1		LS	FIELD OFFICE - ENGINEERS	631.10			
														1				0	1		LS	TESTING EQUIPMENT - CONCRETE	631.16			
														1				0	1		LS	TESTING EQUIPMENT - BITUMINOUS	631.17			
														1				0	1		LU	FIELD OFFICE - TELEPHONE (N.A.B.I.)	631.25			
														0.1			0.9	0	1		LS	MOBILIZATION/DEMobilIZATION	635.11			
																	1	0	1		LS	TRAFFIC CONTROL	641.10			
																	3403	67	3470		LF	DURABLE 4" WHITE LINE	646.40			
																	454	6	460		LF	DURABLE 4" YELLOW LINE	646.41			
																	81	4	85		LF	DURABLE 24" STOP BAR	646.46			
																	12	0	12		EACH	DURABLE LETTER OR SYMBOL	646.50			
																	36	4	40		LF	DURABLE CROSSWALK MARKING W/ DIAGONAL LINES	646.51			
																	9409	141	9550		SY	GEOTEXTILE FOR ROADBED SUBGRADE SEPARATOR	649.11			
																	7411	89	7500		SY	GEOTEXTILE UNDER STONE FILL	649.31			
																	1528	72	1600		SY	GEOTEXTILE FOR UNDERDRAIN TRENCH LINING	649.41			
																	1089	11	1100		SY	GEOTEXTILE FOR SILT FENCE	649.51			
														60			960	20	1040		LB	SEED	651.15			
														125			1950	25	2100		LB	FERTILIZER	651.18			
														0.5			8	0.5	9		TON	AGRICULTURAL LIMESTONE	651.20			
														0.5			8	0.5	9		TON	HAY MULCH (MOD. - STRAW)	651.25			
															107			8	115		CY	CEDAR BARK MULCH (MOD. - PINE BARK MULCH)	651.27			
																	1818	42	1860		CY	TOPSOIL	651.35			
																	185	15	200		CY	TOPSOIL (MOD.)	651.35			
																	95	10	105		CY	TOPSOIL (MOD. - COMPOST)	651.35			
																	1	0	1		LS	EROSION PREVENTION AND SEDIMENT CONTROL PLAN	652.10			
																	250	0	250		HR	MONITORING EROSION PREVENTION AND SEDIMENT CONTROL PLAN	652.20			
																	1	0	1		LU	MAINTENANCE OF EROSION PREVENTION AND SEDIMENT CONTROL PLAN (N.A.B.I.)	652.30			
																	15487	213	15700		SY	EROSION MATTING	654.10			



PROJECT NAME: **FERRISBURGH/VERGS-FERRISBURGH**
 PROJECT NUMBER: **CMG PARK(15)S/STP EH01(21)**
 FILE NAME: quantities.xls PLOT DATE: 6/10/2006
 PROJECT LEADER: WLD DRAWN BY: SRZ
 DESIGNED BY: CSP/GGG CHECKED BY: GAS
 QUANTITY SHEET #2 SHEET 5 OF 65