

# ITEM DETAIL SHEET

VERTICAL GRANITE CURB					CONCRETE SIDEWALK (5")					GUARD RAIL						UNDERDRAIN											
BEGIN STATION	END STATION	POSITION		REMARKS	BEGIN STATION	END STATION	POSITION		REMARKS	BEGIN STATION	END STATION	POSITION		END TREATMENT		BEGIN STATION	END STATION	PIPE NO	POSITION	DIA IN	LENGTH FT	TRENCH		GRAN BK FILL CY	FB EA	MNR PST EA	
		LEFT FT	RIGHT FT				LEFT SY	RIGHT SY				LEFT FT	RIGHT FT	BEGIN EA	END EA							EARTH CY	ROCK CY				
<b>PARKING LOT</b>					<b>PARKING LOT</b>											<b>PARKING LOT</b>											
0+41.7	0+89.7		49.1		0+23	2+50	225									0+48	2+41	U1	LT	6	194	112					
0+89.7	3+29.7		240.0		2+65	3+81	89									0+48	2+41	U2	LT	6	194	112					
3+29.7	3+57.7		28.7		4+01	4+50	42									3+47	2+41	P1	LT	12	103	22					
3+57.7	4+02.4		47.9	Curved												3+47	2+41	P3	LT	12	163	13.5					
4+02.4	4+80.4		82.0	Curved																							
4+80.4	4+92.8		88.1	Curved																							
4+92.8	5+03.7		12.1	Curved																							
5+03.7	5+15.4	39.0																									
5+15.4	5+36.0	27.9																									
5+36.0	5+52.5	50.5																									
5+52.5	5+04.8	92.3		Curved																							
5+04.8	4+59.1	46.8		Curved																							
4+59.1	4+20.0	46.8		Curved																							
4+20.0	4+00.2	32.3																									
4+00.2	3+82.1	61.4		Curved																							
3+82.1	3+54.7	7.4																									
3+54.7	3+49.7	7.9		Curved																							
3+49.7	3+49.7	9.7																									
3+49.7	0+49.9	300.9																									
0+49.9	0+48.8	9.7																									
0+48.8	0+49.3	9.7																									
0+49.3	0+44.3	7.9		Curved																							
0+44.3	0+28.0	6.3																									
0+28.0	0+15.0	36.1		Curved																							
0+15.0	0+15.0	3.3																									
0+15.0	0+36.0	36.1		Curved																							
0+36.0	0+44.3	6.3																									
0+44.3	0+49.3	7.9																									
0+49.3	0+49.3	9.7		Curved																							
0+49.3	0+54.3	5.0																									
0+54.3	1+30.6	70.3																									
1+30.6	2+06.4	69.8																									
2+06.4	2+40.3	27.9																									
2+40.3	2+49.8	12.7		Curved																							
2+49.8	2+40.3	12.6		Curved																							
2+40.3	2+12.4	27.9																									
2+12.4	1+36.6	69.8																									
1+36.6	0+60.3	5.0																									
0+60.3	0+49.3	70.3																									
0+49.3	2+74.3	12.6		Curved																							
2+74.3	2+82.7	6.6																									
2+82.7	3+40.7	60.9																									
3+40.7	3+49.7	11.7																									
3+49.7	3+54.7	7.9		Curved																							
3+54.7	3+08.0	1.3																									
3+08.0	3+81.4	37.0		Curved																							
3+81.4	3+59.0	37.4		Curved																							
3+59.0	3+54.7	110.8																									
3+54.7	3+49.7	7.9		Curved																							
3+49.7	3+49.7	9.7																									
3+49.7	2+88.7	60.9																									
2+88.7	2+74.3	8.5																									
2+74.3	2+64.8	12.5		Curved																							
<b>BUMPER GUARDS (SEE MISCELLANEOUS DETAILS)</b>																											
55+48.8	55+62.1	9.0																									
55+62.1	55+68.1	9.0																									
55+68.1	55+94.5	9.0																									
55+94.5	55+72.0	9.0																									
55+72.0	55+83.4	9.0																									
55+83.4	55+93.8	9.0																									
55+93.8	55+94.1	9.0																									
55+94.1	55+20.3	9.0																									
55+20.3	55+43.5	9.0																									
Sub Totals		1695.6	478.9																								
Project Subtotal		2174.5																									
Rounding		25.5																									
Project Total		2200																									

PAID AS EST. AMOUNT  
ON 10/7/06

FORWARD TO DETAILED SUMMARY OF QUANTITIES

