


QUANTITY SHEET

SUMMARY OF ESTIMATED QUANTITIES										TOTALS			DESCRIPTIONS			DETAILED SUMMARY OF QUANTITIES		
										ROUND	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	QUANTITIES	UNIT	ITEMS
								ARBOR GARDENS	BRENTWOOD PARK									
								375	1711									
										8598	216	10900		CY	COMMON EXCAVATION	203.15		
										31	1	32		CY	EXCAVATION OF SURFACES AND PAVEMENT	203.28		TRENCH EXCAVATION OF EARTH
										2507	53	2560		CY	SAND BORROW	203.31		ARBOR GARDENS
										59				CY	TRENCH EXCAVATION OF EARTH	204.20	59	CY EXCAVATION FOR PIPES AND UNDERDRAIN
										59	1	60		SY	COLD PLANING - BITUMINOUS PAVEMENT	210.10	88	CY EXCAVATION FOR STRUCTURES
										541	1750	6430		CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35	788	CY EXCAVATION FOR PIPES AND UNDERDRAIN
														CY	EXCAVATION FOR DRAINAGE PADS		2	CY EXCAVATION FOR STONE LINED PILOT CHANNEL
														CY	AGGREGATE SHOULDERS, IN PLACE	402.10	16	CY EXCAVATION FOR STONE LINED PILOT CHANNEL
										1	5	14		CWT	EMULSIFIED ASPHALT	404.65	953	CY SUBTOTAL
										115	800	2570		TON	BITUMINOUS CONCRETE PAVEMENT(PG 58-28)	406.25	17	CY ROUNDING
														LU	PRICE ADJUSTMENT ASPHALT CEMENT (NOT A BID ITEM)	406.50	970	CY TOTAL
														CY	CONCRETE, CLASS B	501.25		
														LB	REINFORCING STEEL	507.15		SUBBASE OF DENSE GRADED CRUSHED STONE
														LF	METAL HAND RAILING (MOD.)	525.15	541	CY ARBOR GARDENS
														LF	18" CPEP (SL)	601.2615		US ROUTE 7
														EACH	18" CPEPES	601.7015	1750	CY BRENTWOOD PARK
														EACH	CONCRETE CATCH BASIN WITH CAST IRON GRATE	604.10		US ROUTE 7
														EACH	CHANGING ELEVATION OF DI'S, CB'S, OR MH'S	604.40	2243	CY PARK-AND-RIDE
														EACH	CAST IRON GRATE WITH FRAME, TYPE D	604.47	53	CY PARKING LOT
										307		1130		LF	6" UNDERDRAIN	605.10	1714	CY ACCESS ROAD
														LF	6" UNDERDRAIN CARRIER PIPE	605.20		U.S. ROUTE 7
														EACH	UNDERDRAIN FLUSHING BASINS	605.95	6301	CY SUBTOTAL
														HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I (NOT A BID ITEM)	608.25	129	CY ROUNDING
														HR	TRUCK RENTAL (NOT A BID ITEM)	608.37	6430	CY TOTAL
														MGAL	DUST CONTROL WITH WATER	609.10		BITUMINOUS CONCRETE PAVEMENT (PG 58-28)
														TON	DUST AND ICE CONTROL WITH CALCIUM CHLORIDE	609.15	115	T ARBOR GARDENS
														CY	STONE FILL, TYPE II	613.11		US ROUTE 7
										266		2110		LF	VERTICAL GRANITE CURB	616.21	800	T BRENTWOOD PARK
														SY	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	618.10		US ROUTE 7
														LF	CHAIN LINK FENCE, 6 FEET (MOD.)	620.12	778	T PARK-AND-RIDE
														LF	WOVEN WIRE FENCE WITH WOOD POSTS (SPLIT RAIL FENCE) (MOD.)	620.26	92	T PARKING LOT/BUS LOOP
														LF	REMOVING AND RESETTING FENCE	620.50	738	T ACCESS ROAD
														LF	REMOVE AND RESET GUARD RAIL	621.75		U.S. ROUTE 7
														LF	REMOVAL AND DISPOSAL OF GUARD RAIL	621.80	2523	T SUBTOTAL
														LF	REMOVAL AND DISPOSAL OF GUARD RAIL (MOD.)	621.80	47	T ROUNDING
														HR	UNIFORMED TRAFFIC OFFICERS	630.10	2570	T TOTAL
														HR	FLAGGERS	630.15		
														LS	FIELD OFFICE - ENGINEERS	631.10		
														LS	TESTING EQUIPMENT - CONCRETE	631.16		
														LS	TESTING EQUIPMENT - BITUMINOUS	631.17		
														LU	FIELD OFFICE - TELEPHONE (NOT A BID ITEM)	631.25		



PROJECT NAME: COLCHESTER PARK-AND-RIDE
 PROJECT NUMBER: CMG PARK(18)S
 FILE NAME: quantity sheet.xls
 PROJECT LEADER: WLD
 DESIGNED BY: CSP
 QUANTITY SHEET #1
 PLOT DATE: 9/20/2002
 DRAWN BY: GGG
 CHECKED BY: CSP
 SHEET 6 OF 56