



**PLANT SCHEDULE**

QUANT	COMMON NAME	SCIENTIFIC NAME	SIZE	NOTES
16	RED MAPLE	ACER RUBRUM	2.5 - 3" CAL.	B&B
65	BROADMOOR JUNIPER	JUNIPERUS SABINA 'BROADMOOR'	3 GAL.	4' O.C.
65	KALLAY JUNIPER	JUNIPERUS CHINENSIS 'KALLAYS COMPACTA'	3 GAL.	4' O.C.
630	DAY LILY VARIETIES	HERMACALIS VARIETIES	1 GAL.	18" O.C.

- NOTES**
- CONTRACTOR SHALL INSTALL RED MAPLES BEYOND LIMIT OF SILT FENCE WITH MINIMAL IMPACT TO WETLAND AREA. ALL DISTURBED SOILS SHALL BE REGRADED TO EXISTING CONDITIONS AND ALLOWED TO RESTABILIZE, AS DIRECTED BY THE ENGINEER.
  - CONIFER TREES WITHIN CONSTRUCTION LIMITS WERE TRANSPLANTED BY OTHERS FROM CONSTRUCTION AREA TO NEW LOCATIONS. CONIFERS THAT WERE TRANSPLANTED (THOSE WITH A CIRCLE AROUND THEM) ARE SHOWN IN THEIR NEW LOCATIONS. (34 CONIFER TREES TOTAL)
  - DAY LILIES ARE DESCRIBED IN THE FOLLOWING CATEGORIES:
    - EARLY BLOOMERS - BLOOM FROM EARLY MAY TO JUNE.
    - TALL CULTIVARS - LARGE CLIMBING FOLIAGE, WHEN MATURE FORMS A SMALL SHRUB.
    - LATE BLOOMING CULTIVARS - BLOOM FROM JULY TO THE FIRST FROST.
  - PLANT TALL CULTIVARS IN THE MIDDLE OF AN ISLAND WITH THE EARLY AND LATE BLOOMERS AROUND THE OUTSIDE. PLANT EQUAL NUMBERS OF THE FOLLOWING VARIETIES:
    - EARLY BLOOMERS - FLAT GOLD, EARLY BIRD, H. FLAVA 'LILIOASHEDELUS', GENTLE SHEPARD
    - TALL CULTIVARS - AUNT MARY'S LINEN, BRIGHT IDEA, CHALLENGER, EGGS AND PRESERVES, OLLALIE GOLD, BLACK CHERRY
    - LATE BLOOMERS - AUTUMN GARNET, BUTTERSCOTCH HARVEST, DEEP DARK CAVERNS, PERMANENT PERSIMMON, SEPTEMBER STAR, HALLS PINK, GREEN FLUTTER

**GEOTEXTILE FOR SILT FENCE**  
 PARKING LOT STA. 0+68 TO 1+21, RT.  
 PARKING LOT STA. 1+13 TO 4+78, LT.  
 PARKING LOT STA. 2+69 TO 2+80, RT.  
 PARKING LOT STA. 2+69 TO 2+80, RT.  
 PARKING LOT STA. 4+16 TO 4+27, RT.  
 PARKING LOT STA. 4+41 TO 4+52, LT.  
 PARKING LOT STA. 4+11 TO 4+82, RT.  
 ACCESS ROAD STA. 10+09 TO 12+65, LT.  
 ACCESS ROAD STA. 12+17 TO 12+28, RT.  
 ACCESS ROAD STA. 12+17 TO 12+28, LT.

**HAYBALES FOR INLET PROTECTION**

STA.	OFFSET
2+74	23' LT.
2+74	31' RT.
4+22	31' RT.
4+47	23' LT.
4+84	112' RT.
12+22	17' LT.

**GEOTEXTILE FOR SILT FENCE (INLET PROTECTION)**  
 ACCESS ROAD STA. 10+38, RT.

**LANDSCAPING SUMMARY**

DECIDUOUS TREES		DECIDUOUS TREES		DWARF JUNIPERS		
STA.	OFFSET	STA.	OFFSET	STA.	STA.	LENGTH
1+13	15' LT.	2+73	51' LT.	1+30, 26' LT. TO 4+48, 26' LT.		318'
1+25	41' LT.	3+24	36' LT.	1+56, 27' RT. TO 2+46, 27' RT.		90'
1+38	50' LT.	3+33	55' LT.	3+21, 27' RT. TO 3+66, 27' RT.		45'
1+54	42' LT.	3+99	45' LT.	3+81, 27' RT. TO 4+21, 27' RT.		40'
1+56	58' LT.	4+13	34' LT.			
1+99	53' LT.	4+30	33' LT.			
2+45	48' LT.	4+37	47' LT.	2+56, 27' RT. TO 3+21, 27' RT.		65'
2+62	38' LT.	4+56	26' RT.			
				<b>DAY LILIES</b>		
				STA.	TO STA.	LENGTH
				4+85, 73' RT.		238
				4+21 TO 4+48, RT.		1079

\* SEE TYPICAL SECTION FOR DETAILS

**DH**  
Dufresne-Henry

PROJECT NAME: COLCHESTER PARK-AND-RIDE  
 PROJECT NUMBER: CMG PARK(18)  
 FILE NAME: zk062ero.dgn  
 PROJECT LEADER: WLD  
 DESIGNED BY: CSP  
 EROSION AND LANDSCAPING PLAN

PLOT DATE: 07/08/02  
 DRAWN BY: GGG  
 CHECKED BY: CSP  
 SHEET 34 OF 56

